

1.12 EQUIPMENT CONNECTIONS:

- A. Where electrical connections to equipment require specific locations, such locations shall be obtained from shop drawings and field measurements.

1.13 PRODUCT DELIVERY, STORAGE, HANDLING, & PROTECTION

- A. Inspect materials upon arrival at Project and verify conformance to Contract Documents. Prevent unloading of unsatisfactory material. Handle materials in accordance with manufacturer's applicable standards and suppliers recommendations, and in a manner to prevent damage to materials. Store packaged materials in original undamaged condition with manufacturer's labels and seals intact. Containers which are broken, opened, damaged, or watermarked are unacceptable and shall be removed from the premises.
- B. Equipment and materials shall not be installed until such time as the environmental conditions of the job site are suitable to protect the equipment or materials. Conditions shall be those for which the equipment or materials are designed to be installed. Equipment and materials shall be protected from water, direct sunlight, cold or heat. Equipment or materials damaged or which are subjected to these elements are unacceptable and shall be removed from the premises and replaced.

1.14 CLEANING AND PAINTING

- A. Touch-up scratched or marred surfaces of equipment enclosures with paint furnished by the equipment manufacturers specifically for that purpose.

1.15 GUARANTEE:

- A. All systems and component parts shall be guaranteed for one year from the date of final acceptance of the complete project. Defects found during this guaranteed period shall be promptly corrected at no additional cost to the Owner.
- B. See 16190 for additional warranty required by Generator Manufacturer in addition to the one (1) year warranty noted above.

1.18 SCHEDULING OF OUTAGES

- A. Electrical work requiring interruption of electrical power which would adversely affect the normal operation of the 911 Center coordinated with the Owner.

END OF SECTION 16000