

ENG 2021 SAP LMIG: 2021 Restriping Various County Roads

Val-Del Road – 9.35 miles - Beginning at Joint SR 7 ending at Cook County line

- High build centerline and edge line stripe 5" wide
- 2 Stop Bars (24" Thermoplastic)
- RPM's

Skipper Bridge – 9.20 miles - Beginning at Joint SR 125 ending at Cook County line

- High build centerline and edge line stripe 5" wide
- 3 Stop Bars (24" Thermoplastic)
- 2 Arrows, Type 2 (Thermoplastic)
- RPM's

Union Road – 2.30 miles - Beginning at joint past SR 122 ending at Cook County line

- High build centerline and edge line stripe 5" wide
- RPM's

Old US 41 – 3.5 miles - Beginning at Union Road ending at Hahira City Limits

- High build centerline and edge line stripe 5" wide
- RPM's

Coleman Road North – 1.75 miles - Beginning at Joint SR 7 ending at Crooked Circle

- High build centerline and edge line stripe 5" wide
- 2 Arrows, Type 2 (Thermoplastic)
- RPM's

Shiloh Road – 6.85 miles - Beginning at Vickers Drive ending at Morven Road

- High build centerline and edge line stripe 5" wide
- 1 Stop Bar (24" Thermoplastic)
- RPM's

Cat Creek Road – 2.65 miles - Beginning at Joint SR 125 ending at Radar Site Road

- High build centerline and edge line stripe 5" wide
- 2 Stop Bars (24" Thermoplastic)
- 2 Arrows, Type 2 (Thermoplastic) – (@ SR 125)
- 1 Arrow, Type 2 (Thermoplastic) – (@ River Road Intersection)
- RPM's