

- See GDOT Std. 2406 for apron and toe wall reinforcing (Omit baffle)
- Bed area under aprons and toe walls with 12" # 57 Stone
- Upon removal of aprons if culvert is undermined, must be backfilled with flowable fill
- Protect outlet and inlet ends of aprons with type III rip rap, width of apron and 10' long from apron edge
- Dress out disturbed areas upon completion