
ANY UTILITIES BEING PLACED OR RELOCATED ON STATE ROUTES WILL REQUIRE AN APPROVED GUPS PERMIT.

CONSTRUCTION PLANS

BRIGGSTON ROAD PAVING IMPROVEMENTS

IGTIA # 2101054 PI # 0016275 SGRC-114

LOWNDES COUNTY, GEORGIA L.L. 20, 21, 24, 25, & 26 OF THE 16TH L.D. & L.L. 70 & 71 OF THE 11TH L.D.







DATE: SEPTEMBER 14, 2022 REVISED: JULY 14, 2023

PREPARED BY:



PHONE: 229-249-9113 - www.innovatees.com 2214 N. Patterson Street, Valdosta, GA 31602

Sheet List Table Sheet Number **Sheet Title** COVER **GENERAL NOTES - TYPICAL SECTION** 6 **EXISTING CONDITIONS 5** PLAN & PROFILE 1 PLAN & PROFILE 2 PLAN & PROFILE 3 PLAN & PROFILE 4 PLAN & PROFILE 5 PLAN & PROFILE 6 13 PLAN & PROFILE 7 15 PLAN & PROFILE 9 PLAN & PROFILE 10 **CROSS SECTIONS 1 CROSS SECTIONS 2** 19 **CROSS SECTIONS 3** 20 **CROSS SECTIONS 4** 21 CROSS SECTIONS 5 22 **CROSS SECTIONS 6** 23 CROSS SECTIONS 7 24 EARTHWORK VOLUMES 25 ES&PC 1 ES&PC 2 ES&PC 3 ES&PC 4 29 ES&PC 5 ES&PC DETAIL 1 30 ES&PC DETAIL 2 31 32 ES&PC NOTES 33 NPDES NOTES 34 ES&PC CHECKLIST 35 WATER MAIN EXTENSION 36 WATER MAIN EXTENSION 2 37 **WATER MAIN EXTENSION 3** 38 WATER MAIN EXTENSION 39 WATER MAIN EXTENSION 5 40 WATER MAIN EXTENSION 6 42 **WATER MAIN EXTENSION 8** 43 WATER MAIN EXTENSION 9 44 **WATER MAIN EXTENSION 10** 45 CONSTRUCTION DETAILS 46 **EXISTING RAILROAD CROSSING** 47 PROPOSED RAILROAD CROSSING

CONTACT INFORMATION

LOWNDES COUNTY
ENGINEERING DEPARTMENT
MIKE FLETCHER, PE
229-671-2424

INNOVATE ENGINEERING SOLUTIONS, LLC PROJECT ENGINEER WILLIAM KENT, PE 229-249-9113

LOWNDES COUNTY OFFICIALS

CHAIRMAN
DISTRICT 1
DISTRICT 2
DISTRICT 3
DISTRICT 4
DISTRICT 5

BILL SLAUGHTER
JOYCE EVANS
SCOTT ORENSTEIN
MARK WISENBAKER
DEMARCUS MARSHALL
CLAY GRINER

COUNTY MANAGER COUNTY ENGINEER

PAIGE DUKES MIKE FLETCHER, PE



PROJECT NUMBER 1669



LOCATION MAP

GENERAL CONSTRUCTION NOTES:

- 1. UTILITIES SHOWN HEREON ARE BASED UPON ABOVE GROUND APPURTENANCES ONLY. UTILITY FACILITIES ARE SHOWN SCHEMATICALLY ON THE PLANS AND ARE NOT NECESSARILY ACCURATE AS TO DESCRIPTION, LOCATION, OR ELEVATION. UTILITY FACILITIES, SUCH AS SERVICE LINES OR UNKNOWN FACILITIES, NOT SHOWN ON THE PLANS WILL NOT RELIEVE THE CONTRACTOR OF HIS/HER RESPONSIBILITY UNDER TITLE 25, CHAPTER 9, OFFICIAL CODE OF GEORGIA ANNOTATED. VERIFY THE ELEVATIONS OF EXISTING PIPING, UTILITIES, AND ANY TYPE OF UNDERGROUND OR ENCASED OBSTRUCTION, NOT SPECIFICALLY INDICATED TO BE REMOVED, AS INDICATED OR DISCOVERED IN LOCATIONS TO BE TRAVERSED BY PIPING, DUCTS, AND OTHER WORK TO BE CONDUCTED OR INSTALLED.
- 2. LOWNDES COUNTY WILL BE RESPONSIBLE FOR RELOCATING ALL UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING ALL UTILITY COMPANIES REGARDING LOCATION OF EXISTING UTILITIES AND SHALL BE RESPONSIBLE FOR THE COORDINATION OF WORK WHILE UTILITIES ARE BEING RELOCATED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR OF ANY DAMAGE TO UTILITIES RESULTING FROM WORK PERFORMED BY THE CONTRACTOR. THE CONTRACTOR SHALL TAKE THE NECESSARY STEPS TO MINIMIZE ANY INTERRUPTION OF UTILITY SERVICE TO THE SURROUNDING RESIDENTS. CALL TOLL-FREE 1-800-282-7411, 72 HOURS PRIOR TO THE START OF WORK SO THAT EXISTING UNDERGROUND UTILITIES MAY BE LOCATED.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY LAND OR PROPERTY BEYOND THE PROJECT CONSTRUCTION AREA, WHICH MAY BE SUBJECT TO ANY EFFECTS OR BY-PRODUCTS OF HIS CONSTRUCTION EFFORTS.
- 4. DEMOLITION SHOWN IS A MINIMUM REQUIREMENT. ADDITIONAL DEMOLITION MAY BE REQUIRED TO ACCOMMODATE CONSTRUCTION. THE CONTRACTOR SHALL REPAIR AND REPLACE ALL DAMAGED AND DISTURBED AREAS TO PRE-CONSTRUCTION CONDITIONS, OR BETTER, INCLUDING ALL PAVING, STABILIZED EARTH, SOD, DRIVEWAYS, TREES, SIDEWALKS, CURBS, STORM SEWERS, ETC. WHERE APPLICABLE, THE SAME TYPE OF MATERIAL THAT WAS REMOVED OR DAMAGED DURING CONSTRUCTION SHALL BE USED. IN AREAS OF SIDEWALK AND CURB REMOVAL, REMOVE TO NEAREST JOINT. ALL WORK SHALL BE IN ACCORDANCE WITH ALL APPLICABLE RULES, REGULATIONS, CODES, ETC. CONTRACTOR MUST DISPOSE OF MATERIALS AT A DESTINATION APPROVED BY THE CONTRACTING OFFICER. NO CONSTRUCTION WASTE SHALL BE BURIED ON SITE.
- 5. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY WHEN CONFLICT BETWEEN THE DRAWINGS AND ACTUAL CONDITIONS ARE DISCOVERED DURING THE COURSE OF CONSTRUCTION.
- 6. NO CONSTRUCTION SHALL COMMENCE UNTIL ALL APPLICABLE PERMITS AND REQUIRED EASEMENTS HAVE BEEN OBTAINED.
- 7. CONTRACTOR SHALL PROVIDE ACCURATE AS-BUILTS ON CLEAN COPIES OF CONSTRUCTION PLANS. UTILITY AS-BUILTS SHOULD SHOW ACTUAL INSTALLED LOCATIONS OF MAINS, HYDRANTS, AND SERVICES, CROSSES, & TEES. SERVICES SHALL BE STATIONED FROM MANHOLES FOR SEWER. ALL MANHOLE PIPE INVERTS AND TOP ELEVATIONS SHOULD BE SHOWN. ALL EXISTING UTILITIES DISCOVERED DURING CONSTRUCTION SHALL BE NOTED ON AS-BUILTS AS TO HORIZONTAL AND VERTICAL LOCATION.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INITIATING, SUPERVISING AND MAINTAINING ALL SAFETY PROGRAMS THROUGHOUT THE DURATION OF CONSTRUCTION. ALL BARRICADES, SUFFICIENT LIGHTS, SIGNS AND OTHER TRAFFIC CONTROL METHODS AS NECESSARY FOR THE PROTECTION AND SAFETY OF THE PUBLIC SHALL BE PROVIDED AND MAINTAINED BY THE CONTRACTOR THROUGHOUT THE DURATION OF CONSTRUCTION. TRAFFIC CONTROL METHODS SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (M.U.T.C.D.).
- 9. SAFE TRENCH CONSTRUCTION IS MANDATORY. ALL SLOPES SHALL BE LAID BACK OR SHORED AS NECESSARY.
- 10. THE CONTRACTOR SHALL KEEP RECORDS OF WORK PERFORMED ON A DAILY BASIS. THE CONTRACTOR SHALL PROVIDE ADEQUATE OVERSIGHT AND MANAGEMENT FOR HIS CONSTRUCTION EFFORTS.

- 11. COOPERATION AND COORDINATION BETWEEN ALL CONTRACTORS, UTILITY COMPANIES AND SUBCONTRACTORS ENGAGED IN THE WORK WITHIN AND ADJACENT TO THE CONSTRUCTION IS IMPORTANT FOR THE COMPLETION OF THIS PROJECT IN A TIMELY MANNER. IN THE CASE OF INTERFERENCE BETWEEN THE OPERATIONS OF THE DIFFERENT CONTRACTORS, UTILITY COMPANIES AND SUBCONTRACTORS, THE OWNER WILL BE THE SOLE JUDGE OF THE RIGHTS OF EACH AND THE SEQUENCE OF THE WORK NECESSARY TO EXPEDITE THE COMPLETION OF THIS PROJECT.
- 12. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE CODES, ORDINANCES, RULES, REGULATIONS, AND LAWS OF LOCAL, MUNICIPAL, STATE OR FEDERAL AUTHORITIES HAVING JURISDICTION OVER THIS PROJECT. ALL PERMITS REQUIRED FOR CONSTRUCTION OPERATIONS SHALL BE OBTAINED BY THE CONTRACTOR. ALL ENVIRONMENTAL PERMITS WILL BE HANDLED BY LOWNDES COUNTY.
- 13. THE CONTRACTOR SHALL SAW CUT EXISTING ASPHALT PAVEMENT AS REQUIRED TO PRODUCE A SMOOTH JOINT WITH NEW PAVEMENT.
- 14. THE CONTRACTOR SHALL REMOVE ONLY THOSE TREES AND SHRUBS DEEMED NECESSARY FOR CONSTRUCTION. THE CONTRACTOR SHALL USE CARE TO MINIMIZE DAMAGE TO THE ROOT SYSTEM OF ANY TREES AND SHRUBS NEAR THE CONSTRUCTION AREA.
- 15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION STAKING.
- 16. THE CONTRACTOR IS TO NOTIFY THE ENGINEER AT LEAST 24 HOURS PRIOR TO THE BEGINNING OF EACH PHASE OF CONSTRUCTION. THE CONTRACTOR SHALL ALSO NOTIFY APPLICABLE UTILITY PROVIDERS AT LEAST 24 HOURS PRIOR TO ANY CONSTRUCTION THAT MAY AFFECT THEM.
- 17. THE CONTRACTOR SHALL MAINTAIN, AT ALL TIMES, ADEQUATE AND SAFE ACCESS FOR ALL RESIDENTS AND/OR ADJOINING PROPERTY OWNERS DURING CONSTRUCTION.
- 18. ALL CONCRETE WASHOUT SHALL BE COLLECTED ONSITE AT A DESIGNATED AREA BY THE OWNER FOR OFFSITE DISPOSAL. WASHOUT SHALL BE MAINTAINED EITHER BY BERM OR BY WASHOUT PIT.
- 19. ALL HAZARDOUS MATERIALS / WASTE SHALL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATIONS OR BY THE MANUFACTURER.
- 20. SANITARY WASTE GENERATED FROM PORTABLE UNITS SHALL BE EMPTIED AS REQUIRED TO PROVIDE SANITARY CONDITIONS. ALL SANITARY WASTE DISPOSAL PRACTICES SHALL BE CONDUCTED IN ACCORDANCE WITH STATE AND LOCAL WASTE DISPOSAL REGULATIONS.
- 21. CONTRACTOR SHALL REVIEW, PLAN AND SEQUENCE SITE GRADING AND THE INSTALLATION OF UNDERGROUND UTILITIES TO ENSURE PROPER INSTALLATION AND ELIMINATE POTENTIAL CONFLICTS.

LOWNDES COUNTY GENERAL NOTES:

- ALL WORK SHALL BE DONE IN ACCORDANCE WITH LOWNDES COUNTY STANDARDS AND SPECIFICATIONS.
- 2. CONTRACTOR SHALL NOTIFY THE COUNTY ENGINEER AT LEAST 24 HOURS PRIOR TO THE BEGINNING OF EACH PHASE OF
- 3. CONTRACTOR SHALL NOTIFY THE COUNTY UTILITY DEPARTMENT AT LEAST 24 HOURS PRIOR TO ANY CONNECTION TO THE LOWNDES COUNTY UTILITY SYSTEM.
- 4. ALL EXTENSIONS AND ADDITIONS TO THE COUNTY UTILITY SYSTEM SHALL BE PERFORMED BY A GEORGIA LICENSED UTILITY CONTRACTOR.
- 5. A MINIMUM OF 18" OF VERTICAL AND 10' HORIZONTAL SEPARATION SHALL BE MAINTAINED BETWEEN ALL UTILITIES.
- ANY CROSS CONNECTION TO THE LOWNDES COUNTY WATER SYSTEM IS PROHIBITED.
- 7. ALL TEES AND BENDS SHALL BE DUCTILE IRON.
- 8. CENTERLINE & EDGE LINE STRIPING SHALL CONSIST OF HIGH BUILD STRIPING. STOP BARS SHALL CONSIST OF THERMOPLASTIC TRAFFIC STRIPING.
- 9. ALL SIGNS, POSTS, & HARDWARE WILL BE PROVIDED BY THE CONTRACTOR AND INSTALLED PER M.U.T.C.D. STANDARDS..
- CONTRACTOR SHALL FIELD VERIFY LOCATION OF DRIVEWAYS WITH PROPERTY OWNERS.
- CONTRACTOR SHALL REMOVE ALL STORM PIPING WITHIN THE PROJECT AREA UNLESS NOTED OTHERWISE.
- 12. ALL DRIVEWAYS SHALL BE MAINTAINED AND ACCESSIBLE AT ALL TIMES DURING THE CONSTRUCTION OF THE PROJECT.
- 13. WATER MAIN MATERIAL SHALL BE HDPE DR 11 (200 PSI MINIMUM).
- 14. MAINTAIN 48" MINIMUM COVER OVER WATER MAINS.
- 15. WATER MAIN INSTALLATION DOES INCLUDE WELLPOINT AREAS IF NECESSARY.
- 16. THE CONTRACTOR SHALL BUILD ROAD AND DITCHES TO GRADE AS PER PLANS. NO "BEST FIT" PRACTICES ALLOWED.

1 1/2 INCH ASPHALTIC CONCRETE

12.5 mm SUPERPAVE, LEVEL A

COMPACT UPPER 12' OF SUBGRADE TO 95%

NOTE: CROSS-SLOPE OF DRIVEWAY SHALL BE IN THE SAME DIRECTION AS DITCH FLOW.

TYPICAL DRIVEWAY SECTION

N.T.S.

STANDARD PROCTOR (TYP.)

CONTRACTOR SHALL VERIFY ELEVATIONS PRIOR TO CONSTRUCTION AND NOTIFY ENGINEER IF ACTUAL CONDITIONS DIFFER THAT MAY AFFECT SUCCESSFUL COMPLETION OF IMPROVEMENTS

60' RIGHT OF WAY **~**5" WIDE DOUBLE SOLID YELLOW STRIPING WITH RAISED PAVEMENT MARKERS TYPE I AS PER M.U.T.C.D. 2% SLOPE 5" WIDE SOLID 5" WIDE SOLID WHITE STRIPING WHITE STRIPING SLOPE ---SLOPE 2% TYPICAL DRIVEWAY PROFILE OF SUBGRADE TO 95% N.T.S. STANDARD PROCTOR (TYP.) -1-1/2" RECYCLED ASPHALT CONCRETE 9.5 MM TYPE 2 SUPERPAVE (135 LB/SY) TYPICAL ROADWAY SECTION SUPERPAVE (220 LB/SY) NOT TO SCALE SLOPE TO DRAIN 5/8" REBAR FOUND

SYMBOL LEGEND

1/2" REBAR FOUND 1/2" OPEN TOP PIPE FOUND 5/8" REBAR FOUND W/ CAP #2101 5/8" REBAR FOUND W/ CAP #2284 5/8" REBAR FOUND W/ CAP #3015 CONCRETE MARKER FOUND DEED BOOK PAGE NUMBER FIRE HYDRANT WATER VALVE WATER METER BACK FLOW PREVENTER BACK FLOW PREVENTER POST INDICATOR VALVE IRRIGATION CONTROL VALVE WELL ELECTRIC METER ELECTRIC TRANSFORMER LIGHT POLE UTILITY POLE **GUY WIRE** SANITARY CLEAN OUT SANITARY SEWER MANHOLE GAS VALVE GAS METER MONITORING WELL AIR CONDITIONER UNIT DRAINAGE MANHOLE DROP INLET FLARED END SECTION MAIL BOX FIBER OPTIC PEDESTAL

CABLE TELEVISION PEDESTAL

TELEPHONE PEDESTAL

UNDERGROUND TELEPHONE

TRAFFIC SIGN

— UE — UNDERGROUND ELECTRIC — OU — OVERHEAD UTILITIES

— X —— FENCE LINE

— W — WATER LINE

— GAS LINE

— SS — SANITARY SEWER LINE

GDOT ACCESS MANAGEMENT GENERAL NOTES

- GEORGIA DEPARTMENT OF NATURAL RESOURCES ENVIRONMENTAL PROTECTION DIVISION, EROSION AND SEDIMENTATION CONTROL RULES AND REGULATIONS
- 2. THIS PERMIT IS TO BE STRICTLY CONSTRUED AND NO WORK OTHER THAN THAT SPECIFICALLY DESCRIBED WITHIN IS HEREBY AUTHORIZED. THE WORK AUTHORIZED HEREIN MUST BEGIN WITHIN THREE MONTHS FROM THE DATE OF APPROVAL AND MUST BECOME COMPLETED ON A SCHEDULE SATISFACTORY TO THE DEPARTMENT AND NOT TO EXCEED TWELVE MONTHS FROM THE DATE THE PERMIT WAS APPROVED.
- 5. CURB AND GUTTER MUST MATCH EXISTING. IF EXISTING GUTTER HAS BEEN PAVED
- 6. TRAFFIC CONTROL SIGNS AND DEVICES MUST CONFORM TO THE MANUAL ON
- 7. ADVERTISING SIGNS SHALL NOT BE PLACED ON OR OVERHANGING GDOT
- SPECIFICATIONS.
- 9. DRIVEWAY AND EXTRA WIDENING MUST DRAIN AWAY FROM ROADWAY IN ALL CASES.
- 10. ALL PAVED SHOULDERS SHALL BE SAWCUT AND REMOVED UNLESS IT HAS BEEN VERIFIED THAT THE BASE UNDER THE PAVED SHOULDER IS DEEMED ADEQUATE BY THE PERMIT INSPECTOR. ALL RUMBLE-PAVED SHOULDERS MUST BE OVERLAID.
- 11. GRADE OF DRIVE AND EXTRA WIDENING SHALL MATCH EXISTING ROADWAY
- 12. SIDEWALK AND WHEELCHAIR RAMPS MUST COMPLY WITH GDOT STANDARD A-3.
- 14. MINIMUM BASE AND PAVING FOR RESIDENTIAL DRIVES

1. THIS PLAN IS APPROVED ON THE CONDITION THAT APPLICANT COMPLY WITH 12.5 MM SUPERPAVE (165 LB/SY) GRADED AGGREGATE BASE, 6' THICK

3. THIS PERMIT APPROVED SUBJECT TO SPECIAL REQUIREMENT SHEET ATTACHED AND WILL REMAIN DEPENDENT UPON COMPLIANCE WITH THESE.

4. APPLICANT SHALL RE-GRASS TO GDOT SPECIFICATIONS. ALL STATE RIGHT-OF-WAY AREA WHICH IS DAMAGED OR DISTURBED DURING WORK AUTHORIZED HEREIN.

WITH ASPHALT THEN NEW GUTTER MUST BE PAVED WITH ASPHALT TO MATCH.

UNIFORM TRAFFIC CONTROL DEVICES, CURRENT EDITION.

RIGHT-OF-WAY. 8. ALL WORK ON GDOT RIGHT-OF-WAY MUST COMPLY WITH GDOT STANDARDS AND

13. THIS PERMIT DOES NOT AUTHORIZE ANY WORK ON UTILITIES.

ASPHALT- RECYCLED ASPHALT CONCRETE 9.5 MM TYPE II SUPERPAVE (135 LB/SY) OR

CONCRETE- DRIVEWAY CONCRETE, 6' THICK

15. MINIMUM BASE AND PAVING FOR COMMERCIAL DRIVES:

ASPHALT- RECYCLED ASPHALT CONCRETE 9.5 MM TYPE II SUPERPAVE (135 LB/SY) OR 12.5 MM SUPERPAVE (165 LB/SY) 19 MM SUPERPAVE (220 LB/SY)

GRADED AGGREGATE BASE. 6' THICK CONCRETE- DRIVEWAY CONCRETE. 8' THICK


16. DRIVEWAY MUST HAVE A MINIMUM OF 6 FT GRASS SHOULDERS WITH 6:1 SIDE

17. ALL CURB AND GUTTER ON GDOT RIGHT-OF-WAY MUST COMPLY WITH STANDARD

18. ALL PAVEMENT MARKINGS INSTALLED ON ASPHALT WITHIN GDOT RIGHT-OF-WAY SHALL BE THERMOPLASTIC MATERIAL. HIGH CONTRAST TPE SHALL BE INSTALLED ON CONCRETE.

19. NO UTILITIES ARE ALLOWED UNDER DECELERATION LANES. IF UTILITIES ARE EXISTING, THE PERM/TEE IS RESPONSIBLE FOR RELOCATION.

20. DETECTABLE WARNING SURFACES ARE REQUIRED ON ALL INTERSECTIONS WITH PUBLIC STREETS. SIGNALIZED COMMERCIAL DRIVEWAYS AND COMMERCIAL DRIVEWAYS WITH AN ANNUAL DAILY TRAFFIC OF 25 VEHICLES PER DAY.



ENTRANCE DRIVEWAY

PAVING SECTION

(WITHIN GDOT R/W)

3. SAWCUT EXISTING CONCRETE OR ASPHALT DRIVEWAYS AT R/W. INSTALL NEW DRIVEWAY TO R/W. TAPER TO MATCH EXISTING WIDTH


Itilities Protection Center, Inc. Know what's below. Call before you dig - 12.5 mm SUPERPAVE (TYP.) (SEE 1. REMOVE & REPLACE EXISTING DRIVEWAY PIPES WITH PROPOSED RCP AS SHOWN. 2. SLOPE PROPOSED PIPE TO MATCH DITCH FLOW LINE. NO PIPE WHEN CURB & GUTTER IS USED. . DRIVEWAY LOCATIONS SHOWN ON PLANS ARE APPROXIMATE. CONTRACTOR TO FIELD VERIFY ALL DRIVEWAY LOCATIONS WITH PROPERTY OWNERS. 5. ALL EXISTING IMPROVED DRIVEWAYS SHALL BE REBUILT WITH SIMILAR MATERIALS AND SHALL MATCH EXISTING CONDITIONS WHERE POSSIBLE.





M. WILSON CHECKED BY: B. KENT


SHEET 1 of 47


PROJECT NUMBER 1669
















































































SHEET $17 \, \mathrm{of} \, 47$

PROJECT NUMBER 1669

HORZ. SCALE 1"=30 VERT. SCALE 1"=3' CROSS SECTIONS 1




HORZ. SCALE 1"=30 VERT. SCALE 1"=3' 18 of 47


PROJECT NUMBER
1669

SHEET


DATE: 09/14/2022 DRAWN BY: M. WILSON CHECKED BY: B. KENT




-40 -20 0 20 40




-40 -20 0 20 40



-40 -20 0 20 40



-40 -20 0 20 40









DATE: 09/14/2022 DRAWN BY: M. WILSON CHECKED BY: B. KENT


SHEET $19 \, \mathrm{of} \, 47$


PROJECT NUMBER 1669


HORZ. SCALE 1"=30 VERT. SCALE 1"=3' CROSS SECTIONS 3





































SHEET


 $20\,\mathrm{of}\,47$


PROJECT NUMBER 1669 **CROSS SECTIONS 4**




































SHEET


21 OF 47


PROJECT NUMBER


1669


HORZ. SCALE 1"=30 VERT. SCALE 1"=3'





































SHEET 22 of 47


PROJECT NUMBER 1669


HORZ. SCALE 1"=30 VERT. SCALE 1"=3'


































SHEET 23 of 47

PROJECT NUMBER 1669

HORZ. SCALE 1"=30 VERT. SCALE 1"=3'

		Tota	ıl Volume Tabl	е	
Station	Fill Volume (Cu.Yd.)	Cut Volume (Cu.Yd.)	Cumulative Fill Vol (Cu.Yd.)	Cumulative Cut Vol (Cu.Yd.)	Net Voume (Cu.Yd.)
11+00.00	0.00	0.00	0.00	0.00	0.00
12+00.00	85.64	242.62	85.64	242.62	156.97
13+00.00	97.47	185.38	183.11	428.00	244.89
14+00.00	67.25	159.64	250.36	587.65	337.29
15+00.00	69.81	136.65	320.17	724.29	404.12
16+00.00	75.24	117.29	395.41	841.58	446.17
17+00.00	61.46	127.21	456.87	968.79	511.92
18+00.00	38.63	148.09	495.50	1116.88	621.38
19+00.00	26.55	166.41	522.05	1283.29	761.25
20+00.00	13.15	252.68	535.19	1535.97	1000.78
21+00.00	1.73	358.30	536.92	1894.27	1357.35
22+00.00	1.08	381.36	538.00	2275.63	1737.63
23+00.00	28.35	289.14	566.36	2564.78	1998.42
24+00.00	74.33	156.14	640.69	2720.91	2080.23
25+00.00	171.31	71.69	812.00	2792.60	1980.61
26+00.00	367.76	62.15	1179.76	2854.75	1674.99
27+00.00	471.68	113.24	1651.44	2967.99	1316.55
28+00.00	439.66	169.41	2091.10	3137.41	1046.31
29+00.00	385.26	171.15	2476.36	3308.55	832.19
30+00.00	314.94	93.57	2791.30	3402.12	610.83

	Total Volume Table							
Station	Fill Volume (Cu.Yd.)	Cut Volume (Cu.Yd.)	Cumulative Fill Vol (Cu.Yd.)	Cumulative Cut Vol (Cu.Yd.)	Net Voume (Cu.Yd.)			
71+00.00	60.12	242.70	11759.68	7502.92	-4256.76			
72+00.00	20.71	262.28	11780.39	7765.20	-4015.19			
73+00.00	22.48	209.95	11802.87	7975.15	-3827.72			
74+00.00	50.77	234.28	11853.64	8209.43	-3644.22			
75+00.00	82.69	237.13	11936.34	8446.56	-3489.77			
76+00.00	53.14	211.95	11989.48	8658.51	-3330.96			
77+00.00	77.09	176.21	12066.57	8834.72	-3231.84			
78+00.00	144.75	140.61	12211.31	8975.33	-3235.99			
79+00.00	159.98	99.03	12371.29	9074.35	-3296.94			
80+00.00	139.32	81.34	12510.61	9155.69	-3354.92			
81+00.00	145.80	57.31	12656.41	9213.00	-3443.42			
82+00.00	163.35	47.80	12819.76	9260.80	-3558.97			
83+00.00	84.94	107.86	12904.71	9368.66	-3536.05			
84+00.00	69.27	126.37	12973.98	9495.03	-3478.95			
85+00.00	149.16	99.35	13123.13	9594.37	-3528.76			
86+00.00	120.77	121.01	13243.90	9715.38	-3528.51			
87+00.00	108.13	129.33	13352.03	9844.71	-3507.32			
88+00.00	116.89	124.90	13468.92	9969.61	-3499.31			
89+00.00	103.01	123.28	13571.93	10092.89	-3479.04			
90+00.00	87.67	129.28	13659.60	10222.17	-3437.43			

		Tota	ıl Volume Tabl	e	
Station	Fill Volume (Cu.Yd.)	Cut Volume (Cu.Yd.)	Cumulative Fill Vol (Cu.Yd.)	Cumulative Cut Vol (Cu.Yd.)	Net Voume (Cu.Yd.)
31+00.00	186.67	67.80	2977.97	3469.93	491.96
32+00.00	113.91	84.50	3091.87	3554.43	462.55
33+00.00	108.39	113.44	3200.27	3667.86	467.60
34+00.00	109.14	127.81	3309.41	3795.67	486.27
35+00.00	159.53	98.54	3468.94	3894.22	425.28
36+00.00	214.15	69.16	3683.09	3963.38	280.29
37+00.00	268.42	37.62	3951.51	4001.00	49.49
38+00.00	307.14	21.37	4258.65	4022.37	-236.28
39+00.00	401.80	9.13	4660.45	4031.50	-628.95
40+00.00	534.65	0.00	5195.09	4031.50	-1163.60
41+00.00	567.55	0.00	5762.64	4031.50	-1731.14
42+00.00	539.97	0.00	6302.61	4031.50	-2271.12
43+00.00	529.04	0.00	6831.65	4031.50	-2800.16
44+00.00	508.61	0.00	7340.26	4031.50	-3308.77
45+00.00	441.69	5.77	7781.95	4037.27	-3744.69
46+00.00	197.60	117.29	7979.55	4154.56	-3824.99
47+00.00	13.69	185.15	7993.24	4339.71	-3653.53
48+00.00	74.48	170.50	8067.72	4510.21	-3557.51
49+00.00	127.36	184.10	8195.08	4694.31	-3500.77
50+00.00	91.10	165.88	8286.18	4860.18	-3426.00

Total Volume Table

8320.88

8356.08

8431.12

8596.86

8870.20

9207.33

9584.95

9906.47

10149.20

10368.41

10561.64

10724.90

10811.55

10844.02

10929.63

11091.42

11271.21

11442.75

11583.88

11699.56

205.03

211.25

147.72

82.94

10.31

11.38

22.66

60.79

115.39

171.85

205.73

216.96

232.83

171.98

78.28

64.31

124.85

147.14

51+00.00 34.69

52+00.00 35.20

53+00.00 75.04

54+00.00 | 165.74

55+00.00 273.34

56+00.00 337.13

57+00.00 377.62

58+00.00 321.52

59+00.00 242.72

60+00.00 219.21

61+00.00 193.23

62+00.00 163.26

63+00.00 86.65

64+00.00 32.47

65+00.00 85.62

66+00.00 | 161.79

67+00.00 | 179.79

68+00.00 | 171.54

69+00.00 141.13

70+00.00 115.68

Fill Volume | Cut Volume | Cumulative Fill Vol | Cumulative Cut Vol | Net Voume | (Cu.Yd.) | (Cu.Yd.) | (Cu.Yd.) |

5065.21

5276.46

5424.18

5507.12

5534.59

5544.90

5556.28

5578.94

5639.72

5755.12

5926.97

6132.70

6349.67

6582.49

6754.48

6832.76

6897.07

6988.23

7113.08

7260.22

-3255.66

-3079.62

-3006.94

-3089.74

-3335.61

-3662.43

-4028.68

-4327.54

-4509.47

-4613.29

-4634.67

-4592.20

-4461.89

-4261.53

-4175.16

-4258.67

-4374.14

-4454.52

-4470.80

-4439.34

Total Volume Table					
Station	Fill Volume (Cu.Yd.)	Cut Volume (Cu.Yd.)	Cumulative Fill Vol (Cu.Yd.)	Cumulative Cut Vol (Cu.Yd.)	Net Voume (Cu.Yd.)
91+00.00	62.69	175.67	13722.28	10397.84	-3324.44
92+00.00	40.08	241.37	13762.36	10639.21	-3123.15
93+00.00	109.77	167.76	13872.13	10806.97	-3065.16
94+00.00	98.92	114.60	13971.05	10921.57	-3049.48

NOTE: ALL VOLUMES ARE UNADJUSTED AND USES THE BOTTOM OF PROPOSED BASE AS THE COMPARISON DATUM.

Reineering & Surveying

VE:229-249-9113 - www.innovatees.com

VE:229-249-9113 - www.innovatees.com

VE:229-249-9113 - www.innovatees.com

SEORGINE PROFESSIONA

PROFESSIONA

PROFESSIONA

PROFESSIONA

PROFESSIONA


AMD.


DATE: 09/14/2022 DRAWN BY: M. WILSON CHECKED BY: B. KENT


SHEET 24 OF 47


PROJECT NUMBER 1669


HORZ. SCALE 1"=30 VERT. SCALE 1"=3' EARTHWORK VOLUMES











Ds1 Disturbed Area Stabilization (With MULCHING ONLY)

DEFINITION A TEMPORARY COVER OF PLANT RESIDUES APPLIED TO THE SOIL SURFACE FOR A PERIOD OF SIX (6)

	A TEMPORARY COVER OF PLANT RESIDUES APPLIED TO THE SOIL	MULCHING APPLICATION REQUIREMENTS				
	SURFACE FOR A PERIOD OF SIX (6)	MATERIAL	RATE	DEPTH		
	SURFACE FOR A PERIOD OF SIX (6) MONTHS OR LESS WHEN SEEDING IS NOT PRACTICAL. CONDITIONS THESE AREAS USUALLY CANNOT BE STABILIZED BY ORDINARY CONSERVATION TREATMENT AND MANAGEMENT AND IF LEFT UNTREATED CAN CAUSE SEVERE EROSION SEDIMENT DAMAGE.	STRAW OR HAY	2 1/2 TON/ACRE	6" TO 10"		
		WOOD WASTE, CHIPS, SAWDUST, BARK	6 TO 9 TON/ACRE	2" TO 3"		
		CUTBACK ASPHALT	1200 GAL./ACRE OR 1/4 GAL./SQ. YD.			
		POLYETHYLENE FILM	SECURE WITH SOIL, ANCHORS, WEIGHTS			
		CUTBACK ASPHALT	SEE MANUFACTURER'S RECOMMENDATIONS			
		GEOTEXTILES, JUTE MATTING,	SEE MANUFACTURER'S RECOMMENDATIONS			

SPECIFICATIONS

A. INSTALLATION INSTALL ALL OTHER REQUIRED BMPs FIRST.

2. GRADE SITE, IF POSSIBLE, TO PERMIT THE USE OF EQUIPMENT FOR APPLYING AND ANCHORING

3. LOOSEN COMPACTED SOIL, IF POSSIBLE, TO A DEPTH OF THREE (3) INCHES. 4. APPLY STRAW OR HAY UNIFORMLY, AS SHOWN IN TABLE 1, BY HAND, AND ANCHOR BY PRESSING INTO SOIL OR USE NETTING.

NETTING, ETC.

5. MULCH ON SLOPES GREATER THAN 3% SHOULD BE ANCHORED WITH EMULSIFIED ASPHALT (GRADE AE-5 OR SS-1) OR OTHER SUITABLE TACKIFIER. 6. WOOD WASTE ON SLOPES FLATTER THAN 3:1 DO NOT NEED ANCHORING.

ADD MULCH AS NEEDED TO MAINTAIN THE SUGGESTED DEPTH. IF ORGANIC MULCH IS TO BE LEFT AND INCORPORATED INTO THE SOIL, APPLY 20-30 POUNDS OF NITROGEN IN ADDITION TO THE FERTILIZER REQUIRED FOR VEGETATION.

Disturbed Area Stabilization

(With PERMANENT VEGETATION)

CRITICALLY ERODING AREAS.

THESE AREAS USUALLY CANNOT BE STABILIZED BY ORDINARY

UNTREATED CAN CAUSE SEVERE EROSION SEDIMENT DAMAGE APPLICABLE AREAS ARE THOSE WHERE VEGETATION IS DIFFICULT TO ESTABLISH BY USUAL PLANTING METHODS.

_	SEED	ING RATES FC	R PERMANENT	SEEDING
-	SPECIES	Rate Per	Rate Per Acre*	Planting [

CONSERVATION TREATMENT AND MANAGEMENT AND IF LEFT

SPECIES	1,000 sq.ft.	Per Acre*	Planting Dates**
Bahia	1.4 pounds	60 lbs.	1/1-12/31
Bermuda	0.2 pound	10 lbs.	2/15-7/1
Centipede	Block Sod Only	Block Sod Only	4/1-7/1
Lespedeza	1.7 pounds	75 lbs.	1/1-12/31
Weeping Lovegrass	0.1 pound	4 lbs.	2/1-6/15
Switchgrass	0.9 pound	40 lbs.	3/15-6/1

Inusual site conditions may require heavier seeding rates Seeding dates may need to be altered to fit temperature variations and

Sd2-F) INLET SEDIMENT TRAP - FABRIC (Co)

TO PREVENT SEDIMENT FROM LEAVING THE SITE, OR FROM ENTERING STORM DRAINAGE SYSTEMS, PRIOR TO

SEDIMENT TRAPS SHOULD BE INSTALLED AT OR AROUND ALL STORM DRAIN INLETS THAT RECEIVE RUNOFF FROM

SEDIMENT TRAPS MAY BE CONSTRUCTED ON NATURAL GROUND SURFACE, ON AN EXCAVATED SURFACE, OR ON

APPLICABLE WHERE THE INLET DRAINS A RELATIVELY FLAT AREA (SLOPE NO GREATER THAN 5%) AND SHALL NOT APPLY TO INLETS RECEIVING CONCENTRATED FLOWS. TYPE C SULT FENCE SUPPORTED BY STEEL POSTS SHALL BE USED. THE STAKES SHALL BE SPACED EVENLY AROUND THE PERIMETER OF THE INLET A MAXIMUM OF 3 FEET APART

AND SECURELY DRIVEN INTO THE GROUND, APPROXIMATELY 18 INCHES DEEP. THE FABRIC SHALL BE ENTRENCHEI INCHES AND BACKFILLED WITH CRUSHED STONE OR COMPACTED SOIL. FABRIC AND WIRE SHALL BE SECURELY

THE TRAP SHALL BE INSPECTED DAILY AND AFTER EACH RAIN AND REPAIRS MADE AS NEEDED. SEDIMENT SHALL BE

REMOVED WHEN THE SEDIMENT HAS ACCUMULATED TO ONE-HALF THE HEIGHT OF THE TRAP. FOR EXCAVATED INLE SEDIMENT TRAPS, SEDIMENT SHALL BE REMOVED WHEN ONE-HALF OF THE SEDIMENT STORAGE CAPACITY HAS BEEN

OST TO SEDIMENT ACCUMULATION. SEDIMENT SHALL NOT BE WASHED INTO THE INLET. IT SHALL BE REMOVED FROM HE SEDIMENT TRAP AND DISPOSED OF AND STABILIZED SO THAT IT WILL NOT ENTER THE INLET AGAIN. WHEN THE ONTRIBUTING DRAINAGE AREA HAS BEEN PERMANENTLY STABILIZED, ALL MATERIALS AND ANY SEDIMENT SHALL BE

REMOVED, AND EITHER SALVAGED OR DISPOSED OF PROPERLY. THE DISTURBED AREA SHALL BE BROUGHT TO PROPER GRADE, THEN SMOOTHED AND COMPACTED. APPROPRIATELY STABILIZE ALL DISTURBED AREAS AROUND THE

ASTENED TO THE POSTS, AND FABRIC ENDS MUST BE OVERLAPPED A MINIMUM OF 18 INCHES OR WRAPPED

TOGETHER AROUND A POST TO PROVIDE A CONTINUOUS FABRIC BARRIER AROUND THE INLET.

MACHINE COMPACTED FILL PROVIDED THEY HAVE A NON-ERODIBLE OUTLET. THIS METHOD OF INLET PROTECTION IS

PERMANENT STABILIZATION OF THE DISTURBED AREA

DISTURBED AREAS.

A. GRADING AND SHAPING

ESTABLISH PERMANENT VEGETATIVE COVER ON HIGHLY ERODIBLE OR 1. GRADING AND SHAPING IS NOT NORMALLY REQUIRED WHERE HYDRAULIC SEEDING AND FERTILIZING EQUIPMENT IS TO BE USED. VERTICAL BANKS SHALL BE SLOPED TO ENABLE PLANT ESTABLISHMENTS. . WITH CONVENTIONAL SEEDING AND FERTILIZING, GRADE AND SHAPE WHERE FEASIBLE AND PRACTICAL, SO

THAT EQUIPMENT CAN BE USED SAFELY AND EFFICIENTLY. D. SEEDING 3. CONCENTRATIONS OF WATER THAT WILL CAUSE EXCESSIVE SOIL EROSION WILL BE DIVERTED TO A SAFE 1. HYDRAULIC SEEDING - MIX THE SEED, INOCULANT, FERTILIZER, AND WOOD CELLULOSE OR WOOD PULP B. SEEDBED PREPARATION

WHEN A HYDRAULIC SEEDER IS USED, SEEDBED PREPARATION IS NOT REQUIRED. 2. WHEN CONVENTIONAL SEEDING IS USED, SEEDBED PREPARATION WILL BE DONE AS FOLLOWS:

TILLAGE AT A MINIMUM, SHALL ADEQUATELY LOOSEN THE SOIL TO A DEPTH OF 4 TO 6 INCHES; ALLEVIATE COMPACTION; INCORPORATE LIME AND FERTILIZER; SMOOTH AND FIRM THE

SOIL;ALLOW FOR THE PROPER PLACEMENT OF SEED, SPRIGS, OR PLANTS; AND ALLOW FOR THE ANCHORING OF STRAW OR HAY MULCH. E. MULCHING TILLAGE MAY BE DONE WITH ANY SUITABLE EQUIPMENT TILLAGE MAY BE DONE ON THE CONTOUR WHERE FEASIBLE. IV. ON SLOPES TOO STEEP FOR THE

SAFE OPERATION OF TILLAGE EQUIPMENT, THE SOIL SURFACE WILL BE PITTED OR TRENCHED ACROSS THE SLOPE WITH APPROPRIATE HAND TOOLS TO PROVIDE PLACES 6 TO 8 INCHES APART IN $\,2.$ WHICH SEED MAY LODGE AND GERMINATE. INDIVIDUAL PLANTS WHERE INDIVIDUAL PLANTS ARE TO BE SET, THE SOIL WILL BE WELL PREPARED BY EXCAVATING

HOLES, OPENING FURROWS, OR DIBBLE PLANTING. FOR NURSERY STOCK PLANTS, HOLES SHALL BE LARGE ENOUGH TO ACCOMMODATE ROOTS WITHOUT CROWDING. C. LIME AND FERTILIZER

— 1. AGRICULTURAL LIME SHALL BE APPLIED AS INDICATED BY SOIL TEST OR AT A RATE OF 1 TO 2 TONS PER

LIME SPREAD BY CONVENTIONAL EQUIPMENT WILL BE "GROUND LIMESTONE LIME SPREAD BY HYDRAULIC SEEDING EQUIP. WILL BE "FINELY GROUND LIMESTONE". INITIAL FERTILIZATION REQUIREMENTS FOR EACH SPECIES OR COMBINATION ARE LISTED IN THE MANUAL.

WHEN CONVENTIONAL PLANTING IS DONE, LIME AND FERTILIZER WILL BE APPLIED UNIFORMLY IN ONE OF THE FOLLOWING WAYS: 3.1. APPLY BEFORE LAND PREPARATION SO THAT IT WILL BE MIXED WITH THE SOIL DURING SEEDBED PREPARATION: OR

MIX WITH THE SOIL USED TO FILL THE HOLES, DISTRIBUTE IN FURROWS; OR, BROADCAST AFTER STEEP SURFACES ARE SCARIFIED, PITTED OR TRENCHED.

CONSTRUCTION EXIT

PLASTIC FILTER FABRIC

N.S.A.R.-SIZE R-2 (1.5"-3.5") COARSE AGGREGATE -

CONDITIONS:
THIS PRACTICE IS APPLIED AT APPROPRIATE POINTS OF CONSTRUCTION EGRESS. GEOTEXTILE UNDERLINERS ARE REQUIRED TO STABILIZE AND SUPPORT THE PAD AGGREGATES.

CONSTRUCTION SPECIFICATIONS:
IT IS RECOMMENDED THAT THE ENTRANCE AREA BE EXCAVATED TO A DEPTH OF 3 INCHES AND BE CLEARED OF ALL

DIVERSION RIDGE - ON SITES WHERE THE GRADE TOWARD THE PAVED AREA IS GREATER THAN 2%, A DIVERSION RIDGE 6 TO 8 INCHES HIGH WITH 3:1 SIDE SLOPES SHALL BE CONSTRUCTED ACROSS THE FOUNDATION APPROXIMATELY 15

EOTEXTILE - THE GEOTEXTILE UNDERLINER MUST BE PLACED THE FULL LENGTH AND WIDTH OF THE ENTRANCE.

MUST MEET REQUIREMENTS OF SECTION AASHTO M288-96 SECTION 7.4, STABILIZATION REQUIREMENTS

EOTEXTILE SELECTION SHALL BE BASED ON AASHTO M288-98 SPECIFICATION:

1. FOR SUBGRADES WITH A CBR GREATER THAN OR EQUAL TO 3 OR SHEAR STRENGTH GREATER THAN 90 kPa,

MAINTENANCE:
THE EXIT SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC

RACKED FROM VEHICLES OR SITE ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.

RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 1.5-3.5 INCH STONE, AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEANOUT OF ANY STRUCTURES TO TRAP SEDIMENT, ALL MATERIALS SPILLED, DROPPED, WASHED, OR

OTEXTILE MUST MEET REQUIREMENTS OF SECTION AASHTO M288-96 SECTION 7.3, SEPARATION REQUIREMENTS.

2. FOR SUBGRADES WITH A CBR BETWEEN 1 AND 3 OR SHEAR STRENGTH BETWEEN 30 AND 90 kPa, GEOTEXTILE

ESTABLISH TEMPORARY VEGETATIVE COVER WITH FAST GROWING SEEDINGS ON DISTURBED OR DENUDED AREAS.

THIS PRACTICE IS APPLICABLE ON AREAS SUBJECT TO EROSION FOR JP TO TWELVE MONTHS OR UNTIL THE ESTABLISHMENT OF FINISHED GRADE OR PERMANENT VEGETATIVE COVER. TEMPORARY VEGETATIVE MEASURES SHOULD BE COORDINATED WITH PERMANENT MEASURES TO ASSURE ECONOMICAL AND EFFECTIVE STABILIZATION.

SEEDING RATES FOR TEMPORARY SEEDING

SPECIES	1,000 sq.ft.	Per Acre*	Planting Dates**
Rye	3.9 pounds	3 bu.	9/1-3/1
Ryegrass	0.9 pound	40 lbs.	8/15-4/1
Annual Lespedeza	0.9 pound	40 lbs.	1/15-3/15
Weeping Lovegrass	0.1 pound	4 lbs.	2/15-6/15
Sudangrass	1.4 pounds	60 lbs.	3/1-8/1
Browntop Mi ll et	0.9 pound	40 lbs.	4/1-7/15
Wheat	4.1 pounds	3 bu.	9/15-2/1

* Seeding dates may need to be altered to fit temperature variations and

Disturbed Area Stabilization (With TEMPORARY VEGETATION)

A. GRADING AND SHAPING

EXCESSIVE WATER RUN-OFF MUST BE CONTROLLED BY PLANNED AND INSTALLED EROSION CONTROL PRACTICES SUCH AS CLOSED DRAINS, DITCHES, DIKES, DIVERSIONS, SEDIMENT BASINS AND OTHERS. NO SHAPING OR GRADING IS REQUIRED IF SLOPES CAN BE STABILIZED BY HAND-SEEDED VEGETATION

OR IF HYDRAULIC SEEDING EQUIPMENT IS TO BE USED. B. SEEDBED PREPARATION WHEN A HYDRAULIC SEEDER IS USED, SEEDBED PREPARATION IS NOT REQUIRED.

WHEN USING CONVENTIONAL OR HAND-SEEDING, SEEDBED PREPARATION IS NOT REQUIRED IF THE SOIL MATERIAL IS LOOSE AND NOT SEALED BY RAINFALL WHEN SOIL HAS BEEN SEALED BY RAINFALL OR CONSISTS OF SMOOTH UNDISTURBED CUT SLOPES, THE SOIL SHALL BE PITTED, TRENCHED OR OTHERWISE SCARIFIED TO PROVIDE A PLACE FOR SEED TO

LODGE AND GERMINATE C. LIME AND FERTILIZER AGRICULTURAL LIME IS NOT REQUIRED.

ON REASONABLY FERTILE SOILS OR SOIL MATERIAL, FERTILIZER IS NOT REQUIRED. ON SOILS OR VERY LOW FERTILITY, USE 500 TO 700 POUNDS OF 10-10-10 FERTILIZER OR THE EQUIVALENT PER ACRE (12-16lbs/1,000sq.ft.). IF THE SITE WILL PERMIT, APPLY BEFORE LAND PREPARATION AND DISK, RIP OR CHISEL TO INCORPORATE.

D. SEEDING

SELECT A GRASS OR GRASS-LEGUME MIXTURE SUITABLE TO THE AREA AND SEASON OF THE YEAR. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER-SEEDER, OR HYDRAULIC

E. MULCHING 1. TEMPORARY VEGETATION CAN, IN MOST CASES, BE ESTABLISHED WITHOUT THE USE OF MULCH.

THE INITIAL FERTILIZER WILL BE MIXED WITH SEED, INOCULANT (IF NEEDED) AND WOOD

CONVENTIONAL SEEDING - SEEDING WILL BE DONE ON A FRESHLY PREPARED AND FIRMED SEEDBED. FOR

BROADCAST PLANTING, USE A CULTIPACKER- SEEDER, DRILL, ROTARY SEEDER, OR HAND SEEDING TO

NO-TILL SEEDING IS PERMISSIBLE INTO ANNUAL COVER CROPS WHEN PLANTING IS DONE FOLLOWING

MATURITY OF THE COVER CROP OR IF THE TEMPORARY COVER STAND IS SPARSE ENOUGH TO ALLOW

ADEQUATE GROWTH OF THE PERMANENT SPECIES. THE SEED MUST BE UNIFORMLY DISTRIBUTED AND

USE MULCH ON ALL SLOPES STEEPER THAN 3 PERCENT; WHEN SEEDINGS ARE MADE SO LATE IN THE FALL

AND WINTER THAT GERMINATION CANNOT BE EXPECTED UNTIL SPRING; IN THE BOTTOM OF SPILLWAYS;

WOOD CELLULOSE AND WOOD PULP FIBERS SHALL NOT CONTAIN GERMINATION OR GROWTH INHIBITING FACTORS. THE FIBERS SHALL HAVE A CONTRASTING COLOR TO THE SOIL TO ALLOW VISUAL METERING AND

STRAW OR HAY MULCH MAY BE SPREAD BY BLOWER TYPE EQUIPMENT OR BY HAND. ABOUT 75 PERCENT OF THE SOIL SURFACE SHALL BE COVERED. 4. ANCHOR STRAW OR HAY MULCH BY ONE OF THE FLOWING

PRESS THE MULCH INTO THE SOIL WITH A SPECIAL "PACKER DISK" OR DISK HARROW WITH THE DISKS

PLASTIC MESH OR NETTING WITH NO LARGER THAN ONE INCH BY ONE INCH MESH MAY BE NEEDED TO

ANCHOR STRAW OR HAY MULCH ON UNSTABLE SOILS AND CONCENTRATED FLOW AREAS.

THOROUGHLY WET THE SOIL TO A DEPTH THAT WILL INSURE GERMINATION OF THE SEED.

IRRIGATION IF WATER IS APPLIED, IT MUST BE AT A RATE NOT CAUSING RUNOFF AND EROSION.

FIBER MULCH WITH WATER AND APPLY IN A SLURRY UNIFORMLY OVER THE AREA TO BE TREATED.

FINELY GROUND LIMESTONE WILL BE MIXED WITH WATER AND APPLIED IMMEDIATELY AFTER

CELLULOSE OR WOOD PULP FIBER MULCH AND APPLIED IN A SLURRY.

1. IF WATER IS APPLIED, IT MUST BE AT A RATE NOT CAUSING RUNOFF AND EROSION. THOROUGHLY WET THE SOIL TO A DEPTH THAT WILL INSURE GERMINATION OF THE SEED.

WHEN HYDRAULIC SEEDING EQUIPMENT IS USED:

PLANTED AT THE PROPER DEPTH.

AID IN UNIFORM APPLICATION DURING SEEDING.

(Sd1-S) SEDIMENT BARRIER-SILT FENCE

1.3 LB./FT. MIN. STEEL POST -

TRENCH-IN & BACKFILL BOTTOM OF -

CONSTRUCTION SPECIFICATION

DISPOSED OF BEFORE THE BARRIER IS REMOVED.

FILTER FABRIC

SECTION

ELEVATION

TO PREVENT SEDIMENT CARRIED BY SHEET FLOW FROM LEAVING THE SITE AND ENTERING NATURAL DRAINAGE WAYS

OR STORM DRAINAGE SYSTEM BY SLOWING STORM WATER RUNOFF AND CAUSING THE DEPOSITION OF SEDIMENT AT

BARRIERS SHOULD BE INSTALLED WHERE RUNOFF CAN BE STORED BEHIND THE BARRIER WITHOUT DAMAGING THE FENCE OR THE SUBMERGED AREA BEHIND THE FENCE. SILT FENCE SHALL NOT BE INSTALLED ACROSS STREAMS, DITCHES, WATERWAYS, OR OTHER CONCENTRATED FLOW AREAS.

APPROVED SILT FENCE FABRICS ARE LISTED IN THE GEORGIA DOT QUALIFIED PRODUCTS LIST #36 (QPL-36). THIS FILTER FABRIC IS 36-INCHES WIDE WITH WIRE REINFORCEMENT. THE WIRE REINFORCEMENT IS NECESSARY BECAUSE THIS

FABRIC ALLOWS ALMOST THREE TIMES THE FLOW RATE AS TYPE A SILT FENCE. TYPE C SILT FENCE SHALL BE USED WHERE RUNOFF FLOWS OR VELOCITIES ARE PARTICULARLY HIGH OR WHERE SLOPES EXCEED A VERTICAL HEIGHT OF 10

FEET, PROVIDE A RIPRAP SPLASH PAD OR OTHER OUTLET PROTECTION DEVICE FOR ANY POINT WHERE FLOW MAY TOP

THE SEDIMENT FENCE. ENSURE THAT THE MAXIMUM HEIGHT OF THE FENCE AT A PROTECTED, REINFORCED OUTLET DOES NOT EXCEED 1 FOOT AND THAT THE SUPPORT POST SPACING DOES NOT EXCEED 4 FEET. THE MANUFACTURER

SHALL HAVE EITHER AN APPROVED COLOR MARK YARN IN THE FABRIC OR LABEL THE FABRICATED SILT FENCE WITH BOTH THE MANUFACTURER AND FABRIC NAME EVERY 100 FEET. POSTS MUST BE STEEL. ALONG STREAM BUFFERS AND

SEDIMENT CAN BE REMOVED ONCE IT HAS ACCUMULATED TO ONE-HALF THE ORIGINAL HEIGHT OF THE BARRIER. FILTER FABRIC SHALL BE REPLACED WHENEVER IT HAS DETERIORATED TO SUCH AN EXTENT THAT THE EFFECTIVENESS OF THE

FABRIC IS REDUCED. TEMPORARY SEDIMENT BARRIERS SHALL REMAIN IN PLACE UNTIL DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED. ALL SEDIMENT ACCUMULATED AT THE BARRIER SHALL BE REMOVED AND PROPERLY

OTHER SENSITIVE AREAS, TWO ROWS OF TYPE C SILT FENCE WITH HAYBALES STAKED BETWEEN SHALL BE USED.

WOVEN WIRE FENCE BACKING -

D.O.T. APPROVED FILTER FABRIC NAILED, STAPLED

POCKETED OR OTHERWISE SECURELY FASTENED TO POSTS

3.3. SYNTHETIC TACKIFIERS OR BINDERS.


AND ON ROADBANKS

3.1. FMULSIFIFD ASPHALT

DISTRIBUTE THE SEED UNIFORMLY OVER THE AREA TO BE TREATED.

FALL AND WINTER PLANTINGS MAY INCLUDE 1/2 BU. OF RYE OR WHEAT.

STORM DRAIN OUTLET PROTECTION



1. La IS THE LENGTH OF THE RIPRAP APRON 2. D = 1.5 TIMES THE MAXIMUM STONE

3. IN A WELL-DEFINED CHANNEL EXTEND THE APRON UP THE CHANNEL BANKS TO AN ELEVATION OF 6" ABOVE THE MAXIMUM TAILWATER DEPTH OR UP TO THE TOP OF THE BANK, WHICHEVER IS LESS 4. A FILTER BLANKET OR FILTER FABRIC SHOULD BE INSTALLED BETWEEN THE RIPRAP AND SOIL FOUNDATION

AVED AND/OR RIPRAPPED CHANNEL SECTIONS, PLACED BELOW STORM DRAIN OUTLETS.

IS STANDARD APPLIES TO ALL STORM DRAIN OUTLETS, ROAD CULVERTS, PAVED CHANNEL OUTLETS, ETC., DISCHARGING INTO NATURAL OR CONSTRUCTED CHANNELS. ANALYSIS AND/OR TREATMENT WILL EXTEND FROM THE END OF THE CONDUIT. CHANNEL OR STRUCTURE TO THE POINT OF ENTRY INTO AN EXISTING STREAM OR PUBLICLY MAINTAINED DRAINAGE SYSTEM.

ENSURE THAT THE SUBGRADE FOR THE FILTER AND RIPRAP FOLLOWS THE REQUIRED LINES AND GRADES SHOWN IN THE PLAN. COMPACT ANY FILL REQUIRED IN THE SUBGRADE TO THE DENSITY OF THE SURROUNDING UNDISTURBED MATERIAL. LOW AREAS IN THE SUBGRADE ON UNDISTURBED SOIL MAY ALSO BE FILLED BY INCREASING THE RIPRAP THICKNESS THE RIPRAP AND GRAVEL FILTER MUST CONFORM TO THE SPECIFIED GRADING LIMITS SHOWN ON THE PLANS. GEOTEXTILE MUST MEET DESIGN REQUIREMENTS AND BE PROPERLY PROTECTED FROM PUNCHING OR TEARING DURING INSTALLATION. REPAIR ANY DAMAGE BY REMOVING THE RIPRAP AND PLACING ANOTHER PIECE OF FILTER FABRIC OVER THE DAMAGED AREA. ALL CONNECTING JOINTS SHOULD OVERLAP A MINIMUM OF 1 FOOT. IF THE DAMAGE IS EXTENSIVE, REPLACE THE

THE MINIMUM THICKNESS OF THE RIPRAP SHOULD BE 1.5 TIMES THE MAXIMUM STONE DIAMETER

IMMEDIATELY AFTER CONSTRUCTION, STABILIZE ALL DISTURBED AREAS WITH VEGETATION

CONSTRUCT THE APRON ON ZERO GRADE WITH NO OVERFALL AT THE END. MAKE THE TOP OF THE RIPRAP AT THE DOWNSTREAM END LEVEL WITH THE RECEIVING AREA OR SLIGHTLY BELOW ENSURE THAT THE APRON IS PROPERLY ALIGNED WITH THE RECEIVING STREAM AND PREFERABLY STRAIGHT THROUGHOUT ITS LENGTH. IF A CURVE IS NEEDED TO FIT SITE CONDITIONS, PLACE IT IN THE UPPER SECTION OF THE APRON.

STONE QUALITY - SELECT STONE FOR RIPRAP FROM FIELD STONE OR QUARRY STONE. THE STONE SHOULD BE HARD, ANGULAR, AND HIGHLY WEATHER-RESISTANT. THE SPECIFIC GRAVITY OF FILTER - INSTALL A FILTER TO PREVENT SOIL MOVEMENT THROUGH THE OPENINGS IN THE RIPRAP. THE FILTER SHOULD CONSIST OF A GRADED GRAVEL LAYER OR A SYNTHETIC FILTER CLOTH

NSPECT RIPRAP OUTLET STRUCTURES AFTER HEAVY RAINS TO SEE IF ANY EROSION AROUND OR BELOW THE RIPRAP HAS TAKEN PLACE OR IF STONES HAVE BEEN DISLODGED. IMMEDIATELY MAKE

Du DUST CONTROL WATER TANK DUST CONTROL ON DISTURBED AREAS

SPRAY-ON ADHESIVE APPLICATION REQUIREMENTS

CITY TO A PRICE OF THE PRICE OF					
ADHESIVE	WATER DILUTION	NOZZLE TYPE	APPLICATION (GAL./ACRE)		
ANIONIC ASPHALT EMULSION	7:1	COARSE SPRAY	1,200		
LATEX EMULSION	12.5:1	FINE SPRAY	235		
RESIN-IN- WATER EMULSION	4:1	FINE SPRAY	300		

DEFINITION CONTROLLING SURFACE AND AIR MOVEMENT OF DUST ON CONSTRUCTION SITES, ROADS, AND DEMOLITION SITES.

 TO PREVENT SURFACE AND AIR MOVEMENT OF DUST FROM EXPOSED SOIL SURFACES. • TO REDUCE THE PRESENCE OF AIRBORNE SUBSTANCES WHICH MAY BE HARMFUL OR INJURIOUS TO HUMAN HEALTH, WELFARE, OR SAFETY, OR TO ANIMALS OR

CONSTRUCTION SPECIFICATION APPLY ACCORDING TO APPROVED PLAN. IF SHOWN MULCH DISTURBED AREAS AND TACKIFY WITH RESINS

SUCH AS ASPHALT, CURASOL OR TERRATACK ACCORDING TO MANUFACTURER'S RECOMMENDATIONS. STABILIZE DISTURBED AREA WITH TEMPORARY OR PERMANENT VEGETATION.


• IRRIGATE DISTURBED AREAS UNTIL SURFACE IS WET COVER SURFACE WITH CRUSHED STONE OR GRAVEL APPLY CALCIUM CHLORIDE AT A RATE TO KEEP SURFACE


 APPLY SPRAY-ON ADHESIVES TO MINERAL SOILS (NOT) MUCK SOILS) AS DESCRIBED IN TABLE 1.

MAINTENANCE

 PROHIBIT TRAFFIC ON SURFACE AFTER SPRAYING. SUPPLEMENT SURFACE COVERING AS NEEDED.

Cd-H TYPICAL STRAW BALE CHECK DAM






BALE ENDS <u>TIGHTLY</u> ABUTTING THE ADJACENT BALES.

<u>REMOVE</u> #4 REBAR AFTER STRAW BALES ARE NO LONGER IN PLACE.


POINT C OF SECTION B-B SHOULD <u>ALWAYS</u> BE HIGHER THAN POINT D.




O PREVENT SEDIMENT CARRIED BY SHEET FLOW FROM LEAVING THE SITE AND ENTERING NATURAL DRAINAGE WAYS OR STORM DRAINAGE SYSTEM BY SLOWING STORM WATER RUNOFF AND CAUSING THE DEPOSITION OF SEDIMENT AT THE

BARRIERS SHOULD BE INSTALLED WHERE RUNOFF CAN BE STORED BEHIND THE BARRIER WITHOUT DAMAGING THE FENCE OR THE SUBMERGED AREA BEHIND THE FENCE. SILT FENCE SHALL NOT BE INSTALLED ACROSS STREAMS, DITCHES, WATERWAYS, OR OTHER CONCENTRATED FLOW AREAS. CONSTRUCTION SPECIFICATION
APPROVED SILT FENCE FABRICS ARE LISTED IN THE GEORGIA DOT QUALIFIED PRODUCTS LIST #36 (QPL-36). THIS 36-INCH
WIDE FILTER FABRIC SHALL BE USED ON DEVELOPMENTS WHERE THE LIFE OF THE PROJECT IS GREATER THAN OR EQUAL TO SIX MONTHS. THE MANUFACTURER SHALL HAVE EITHER AN APPROVED COLOR MARK YARN IN THE FABRIC OR LABEL THE FABRICATED SILT FENCE WITH BOTH THE MANUFACTURER AND FABRIC NAME EVERY 100 FEET. POST INSTALLATION SHALL START AT THE CENTER OF THE LOW POINT WITH REMAINING POSTS SPACED 6 FEET APART. POSTS CAN BE WOOD OR STEEL.

SEDIMENT CAN BE REMOVED ONCE IT HAS ACCUMULATED TO ONE-HALF THE ORIGINAL HEIGHT OF THE BARRIER. FILTER FABRIC SHALL BE REPLACED WHENEVER IT HAS DETERIORATED TO SUCH AN EXTENT THAT THE EFFECTIVENESS OF THE ABRIC IS REDUCED. TEMPORARY SEDIMENT BARRIERS SHALL REMAIN IN PLACE UNTIL DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED. ALL SEDIMENT ACCUMULATED AT THE BARRIER SHALL BE REMOVED AND PROPERLY DISPOSED OF BEFORE THE BARRIER IS REMOVED.



BALES SHOULD BE BOUND WITH WIRE OR NYLON STRING AND SHOULD BE PLACED IN ROWS WITH



DATE: M. WILSON

SHEET

PROJECT NUMBER 1669


ES&PC DETAIL 1



LEVEL II CERT. 8141

CHECKED BY: B. KENT

 $30 \, \mathrm{of} \, 47$



Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
AdA	Albany sand, 0 to 2 percent slopes	20.4	3.0
Da	Dasher muck	60.4	8.8
FsB	Fuquay loamy sand, 0 to 5 percent slopes	100.5	14.6
Jo	Johnston loam	48.0	7.0
Le	Leefield loamy sand, 0 to 2 percent slopes	199.7	29.0
Mn	Mascotte sand	38.5	5.6
Oa	Olustee sand	11.6	1.7
Pe	Pelham loamy sand, 0 to 2 percent slopes, frequently flooded	110.0	16.0
Se	Stilson loamy sand, 0 to 2 percent slopes	17.6	2.6
TfA	Tifton loamy sand, 0 to 2 percent slopes	2.7	0.4
TfB	Tifton loamy sand, 2 to 5 percent slopes	72.6	10.6
W	Water	5.8	0.8
Totals for Area of Interest		688.0	100.0

		INSTALLATION OF PERIMETER CONTROL		
		CLEARING AND GRUBBING		
		PRELIMINARY GRADING		
LOW DIAMETER TW La W1 W2	D50 dmax D	INSTALLATION OF INTERMEDIATE E&S CONTROLS		
28 30" MIN. 14' 7.5' 16.5' 200 DOUBLE 5'x4' (60" EQUIV) MIN. 32' 20' 42' 7.6 DOUBLE 18" MIN. 9' 6.0' 12'	0.5' 0.75' 1.13' 1.0' 1.50' 2.25' 0.5' 0.75' 1.13'	ROAD CONSTRUCTION		
98 DOUBLE 48" MIN. 26' 16' 34'	0.9' 1.35' 2.03'	UTILITY CONSTRUCTION		
		FINISHED GRADING		
MENT STORAGE:		FINAL STABILIZATION		
IRED: C.Y./AC X 11.50 AC = 771 C.Y.		VEGETATION AND MULCHING		
IDED:		REMOVE TEMPORARY E&SC MEASURES		

SEDIMENT STO	RAGE:		
REQUIRED: 67 C.Y./AC X 1	.50 AC = 771 C.Y.		
PROVIDED: IN SILT FENCE	9,141 L.F. X 0.17 C.\	/./L.F = 1,554 C.Y.	
	9,141 L.F. X 0.17 C.\	/./L.F = 1,554 C.Y.	

	HYDROLOGY STUDY				
	PRE-DEVELOPED	POST DEVELOPED			
C-FACTOR	0.50	0.60			

Utilities Protection Center, Inc.

Know what's below. Call before you dig.

WITHIN 200 FEET OF THIS SITE.

THERE ARE NO STATE WATERS

WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY SECTION 404 PERMIT

ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.

RATIONALE EXPLAINING REASON THAT A SEDIMENT BASIN SHALL NOT BE USED ON THIS PROJECT.

A SEDIMENT BASIN WILL NOT BE USED ON THIS PROJECT DUE TO THE LIMITED SIZE OF THE CONSTRUCTION SITE. LAND DISTURBING ACTIVITIES WILL BE CONDUCTED WITHIN THE EXISTING RIGHT-OF-WAY OF BRIGGSTON ROAD. BMP's WILL BE EMPLOYED BY THE CONTRACTOR TO LIMIT EROSION AND SEDIMENT AT ITS SOURCE.

ADJACENT AREAS SHOULD NOT BE AFFECTED PROVIDED PROPER BMP'S ARE INSTALLED AND MAINTAINED FOR THE LIFE OF THE PROJECT.

THIS CONSTRUCTION PROJECT DOES NOT INVOLVE MASS GRADING. THE INITIAL SEDIMENT STORAGE REQUIREMENTS, PERIMETER CONTROL BMP's, AND FINAL BMP's ARE THE SAME. THEREFORE, THIS PLAN HAS COMBINED ALL THE BMP'S INTO A SINGLE PHASE PLAN.

I certify under penalty of law that this document was prepared after a site visit to the location described herein by

MONTHS

"I certify that the permittee's Erosion, Sedimentation and Pollution Control Plan provides for an appropriate and comprehensive system of best management practices required by the Georgia Water Quality Control Act and the document "Manual for Erosion and Sediment Control in Georgia," (Manual) published by the Georgia Soil and Water Conservation Commission as of January 1 of the year in which the land disturbing activity was permitted, provides for sampling of the receiving water(s) or the sampling of the storm water outfalls and that the designed system of best management practices and sampling methods is expected to meet the requirements contained in the General NPDES Permit No. GAR100002."

"I certify that the permittee's Erosion, Sedimentation and Pollution Control Plan provides for the monitoring of: (a) all perennial and intermittent streams and other water bodies shown on the USGS topographic map and all other field verified perennial and intermittent streams and other water bodies, or (b) where any such specific identified perennial and intermittent stream and other water body is not proposed to be sampled, I have determined in my professional judgement, utilizing the factors required in the General NPDES Permit No. GAR 100002, that the increase in the turbidity of each specific identified sampled receiving water will be representative of the increase in the turbidity of a specific identified un-sampled receiving water."

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that certified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

"I certify that georgia's current 305(b)/303d list documents have been consulted to determin if the project discharges to an impaired stream segment or within 1 mile of a biota impaired stream segment."

myself or my authorized agent, under my direct supervision."

ACTIVITY SCHEDULE

- 1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH LOWNDES COUNTY STANDARDS AND SPECIFICATIONS 2. THE CONTRACTOR IS TO VERIFY ALL ELEVATIONS OF PROPOSED STRUCTURES AND CURBING TO ENSURE
- POSITIVE DRAINAGE PRIOR TO CONSTRUCTION.
- ALL DISTURBED AREAS ARE TO BE GRASSED AND MULCHED <u>IMMEDIATELY</u> UPON COMPLETION OF GRADING.
 THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION CONTROL
- MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND DISTURBING ACTIVITIES. 5. EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
- 6. ALL EROSION CONTROL MEASURES SHALL BE INSPECTED BY THE CONTRACTOR DAILY. ANY DAMAGES OBSERVED
- SHALL BE REPAIRED BY THE END OF THAT DAY. OWNER/DEVELOPER:
 - LOWNDES COUNTY BOARD OF COMMISSIONERS
 - 327 N. ASHLEY STREET VALDOSTA, GA 31601
- 8. 24 HR/CONTACT:
 - MIKE FLETCHER MFLETCHER@LOWNDESCOUNTY.COM
- PH: (229) 671-2424 9. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE SHALL BE DEPOSITED IN A DUMPSTER. THE DUMPSTER
- SHALL BE EMPTIED FULL. NO CONSTRUCTION WASTE SHALL BE BURIED ON SITE. 10. ALL CONCRETE WASHOUT SHALL BE COLLECTED ONSITE AT A DESIGNATED AREA BY THE DEVELOPER OR
- CONTRACTOR FOR OFFSITE DISPOSAL. WASHOUT SHALL BE MAINTAINED EITHER BY BERM OR BY WASHOUT PIT. WASH OUT OF DRUM IS PROHIBITED.
- 11. ALL HAZARDOUS MATERIAL/WASTE SHALL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR BY MANUFACTURER.
- 12. SANITARY WASTE GENERATED FROM PORTABLE UNITS SHALL BE EMPTIED AS REQUIRED TO PROVIDE SANITARY CONDITIONS. ALL SANITARY WASTE DISPOSAL PRACTICES SHALL BE CONDUCTED IN ACCORDANCE WITH STATE AND LOCAL WASTE DISPOSAL REGULATIONS.
- 13. SILT FENCE SHALL BE INSTALLED ON ALL DOWN SLOPES OF DISTURBED AREAS.
- 14. USE OF MULCH TO STABILIZE AREAS LEFT DISTURBED FOR MORE THAN 14 CALENDAR DAYS.

TOTAL SITE AREA: ±11.50 AC. TOTAL DISTURBED AREA: ±11.50 AC.

DEVELOPMENT REFERENCE

PRIMARY PERMITTEE:
LOWNDES COUNTY BOARD OF COMMISSIONERS 327 N. ASHLEY STREET VALDOSTA, GA 31601

INNOVATE ENGINEERING SOLUTIONS, LLC. 2214 N. PATTERSON STREET VALDOSTA, GA 31604 PH: (229) 249-9113

24-HOUR CONTACT: MIKE FLETCHER PH: (229) 671-2424

NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25-FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

THIS IS IN COMPLIANCE WITH WASTE DISPOSAL, SANITARY SEWER AND SEPTIC TANK REGULATIONS.

LEVEL II CERT. 8141 DATE: 09/14/2022 DRAWN BY: M. WILSON CHECKED BY: B. KENT

> SHEET $31 \, \mathrm{of} \, 47$

PROJECT NUMBER 1669

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND REPORTED TO THE DESIGN PROFESSIONAL IMMEDIATELY. PRACTICES PRIOR TO, OR CONCURRENT WITH LAND-DISTURBING ACTIVITIES.

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR

AMENDMENTS / REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMP'S WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.

CONTRACTOR SHALL ENSURE THAT NO SEDIMENT RESULTING FROM CONSTRUCTION ACTIVITIES LEAVES THE PROJECT SITE AND ENTERS ADJACENT PROPERTIES.

INITIAL PHASE

SEDIMENT SOURCE.

EROSION CONTROL NOTES

PRIOR TO THE LAND DISTURBING CONSTRUCTION, THE CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE AREA SITE

THE OWNER AGREES TO PROVIDE AND MAINTAIN OFF-STREET PARKING ON THE SUBJECT PROPERTY DURING THE ENTIRE CONSTRUCTION PERIOD.

NO STAGING AREAS, MATERIALS, STORAGE, CONCRETE WASH OUT AREAS, OR DEBRIS BURN AND BURIAL HOLES SHALL BE LOCATED WITHIN 500 FEET OF DESIGNATED TREE PROTECTION AREAS.

A COPY OF THE APPROVED LAND DISTURBANCE PLAN AND PERMIT SHALL BE PRESENT ON THE SITE AT ALL TIMES.

AND PERFORMANCE TO INSURE THAT LAND STRIPPED OF ITS NATURAL COVER IS EXPOSED ONLY IN SMALL QUANTITIES.

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH LAND-DISTURBING ACTIVITIES. ALL GRADED AREAS SHALL BE APPLIED WITH VEGETATIVE COVER AS SOON AS FINAL GRADE IS ACHIEVED.

PRIOR TO COMMENCING LAND DISTURBANCE ACTIVITY, THE LIMITS OF LAND DISTURBANCE SHALL BE CLEARLY AND ACCURATELY DEMARCATED WITH STAKES, RIBBONS, OR OTHER APPROPRIATE MEANS. THE LOCATION AND EXTENT OF ALL AUTHORIZED LAND DISTURBANCE ACTIVITY SHALL MULCH OR TEMPORARY GRASSING SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN 7 DAYS OF LAND DISTURBANCE. BE DEMARCATED FOR THE DURATION OF THE CONSTRUCTION ACTIVITY. NO LAND DISTURBANCE SHALL OCCUR OUTSIDE THE APPROVED LIMITS

ALL DISTURBED AREAS LEFT MULCHED AFTER 30 DAYS SHALL BE STABILIZED WITH TEMPORARY GRASSING. INDICATED ON THE APPROVED PLANS.

FROM THE SITE OR ONTO ANY PUBLIC ROADWAY.

THE FOLLOWING INITIAL EROSION CONTROL MEASURES SHALL BE IMPLEMENTED PRIOR TO ANY OTHER CONSTRUCTION ACTIVITY.

- 1. THE CONSTRUCTION EXIT, CONSISTING OF A MINIMUM PAD SIZE OF 20 FEET BY 50 FEET WITH A MINIMUM OF 6" THICK STONE, SHALL BE PLACED AS SHOWN ON THE PLAN. THE STONE SIZE SHOULD CONSIST OF COURSE AGGREGATE BETWEEN 1-1/2" & 3-1/2" IN DIAMETER AND OVERLAY ON A GEOTEXTILE UNDERLINER, THE GEOTEXTILE UNDERLINER SHALL MEET THE REQUIREMENTS OF ASHTO M268-96, SECTION 7.3 SEPARATION NEW CHANNELS HAVE DEVELOPED.
- 2. IMMEDIATELY AFTER THE ESTABLISHMENT OF CONSTRUCTION ENTRANCE/EXITS, ALL PERIMETER EROSION CONTROL AND STORM WATER MANAGEMENT DEVICES SHALL BE INSTALLED AS SHOWN ON THE CLEARING PHASE EROSION CONTROL PLAN.
- 3. SILT FENCE SHOULD BE INSTALLED AT THE PERIMETER OF THE DISTURBED AREA AS SHOWN ON THE PLAN. THE SILT FENCE SHOULD BE PLACED IN ACCORDANCE WITH THE MANUAL FOR EROSION CONTROL IN GEORGIA, TABLE 6-20.2. THE SILT FENCE SHOULD BE KEPT ERECT AT REMOVED WHEN ACCUMULATION REACHES 1/2 HEIGHT OF THE BARRIER. THE PERIMETER SILT FENCE SHOULD BE INSPECTED DAILY FOR ANY FAILURES. ANY FAILURES OF SAND FENCING SHOULD BE REPAIRED IMMEDIATELY.
- 4. INLET SEDIMENT PROTECTION MEASURES SHALL BE INSTALLED ON ALL EXISTING STORM STRUCTURES AS SHOWN ON THE PLAN. SEE SEPARATE DETAILS FOR SPECIFICS ON TYPE OF INLET PROTECTION SPECIFIED.
- 5. STONE CHECK DAMS SHALL BE INSTALLED IN AREAS OF CONCENTRATED FLOWS AS SHOWN ON THE PLAN.
- 6. TREE PROTECTION FENCING SHOULD BE INSTALLED PRIOR TO THE START OF ANY LAND DISTURBANCE ACTIVITY AND MAINTAINED UNTIL FINAL FINAL PHASE LANDSCAPE IS INSTALLED. THE TREE PROTECTION FENCING SHOULD BE INSPECTED DAILY. ANY FAILURES OF SAND FENCING SHOULD BE REPAIRED IMMEDIATELY.

WITHIN 7 DAYS OF INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMP's. THE SITE CONTRACTOR SHALL SCHEDULE AN INSPECTION BY THE PROJECT DESIGN PROFESSIONAL. NO OTHER CONSTRUCTION ACTIVITIES SHALL OCCUR UNTIL THE PROJECT DESIGN PROFESSIONAL APPROVES THE INSTALLATION OF SOIL EROSION CONTROL MEASURES. IF UNFORESEEN CONDITIONS EXIST IN IT WILL NOT ENTER THE INLETS AGAIN. THE FIELD THAT WARRANT ADDITIONAL EROSION CONTROL MEASURES, THE CONTRACTOR MUST CONSTRUCT ANY ADDITIONAL EROSION DEVICES MULCH OR TEMPORARY GRASSING SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN 7 DAYS OF LAND DISTURBANCE. DEEMED NECESSARY BY THE SITE INSPECTION.

AFTER APPROVAL OF THE INITIAL EROSION CONTROL INSTALLATION, THE CONTRACTOR MAY PROCEED WITH CLEARING AND GRUBBING ACTIVITIES. AS CLEARING PERMITS THE CONTRACTOR SHALL CONTROL EROSION AND STORM WATER RUN OFF.

THE CONTRACTOR CAN UTILIZE CLEARED TREES AS BARRIER BRUSH SEDIMENT CONTROL IN AREAS SHOWN ON PLAN WHERE INITIAL GRADING

NO BURN OR BURY PITS SHALL BE PERMITTED ON THE CONSTRUCTION SITE WITHOUT WRITTEN PERMISSION BY THE OWNER AND/OR THE

ENGINEER OF RECORD.

ACTIVITIES WILL NOT OCCUR.

ADDITIONAL SILT BARRIERS MUST BE PLACED AS SHOWN ON THE PLAN AS ACCESS IS OBTAINED DURING CLEARING. NO GRADING SHALL TAKE PLACE UNTIL SILT BARRIER INSTALLATION AND SEDIMENT PONDS ARE CONSTRUCTED AS SHOWN ON THE CLEARING PHASE EROSION CONTROL

ALL SILT FENCE MUST MEET THE REQUIREMENTS OF SECTION 171-TEMPORARY SILT FENCE FOR THE DEPARTMENT OF TRANSPORTATION, STATE OF GEORGIA, STANDARD SPECIFICATIONS, 1983 EDITION.

ALL ITEMS IN THIS SECTION OF THE SPECIFICATIONS SHALL MEET THE REQUIREMENTS AS SET FORTH IN SECTION 161, 162, 163, AND 164 OF THE GEORGIA D.O.T. STANDARD SPECIFICATIONS, FOR ROADS AND BRIDGES.

MULCH OR TEMPORARY GRASSING SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN 7 DAYS OF LAND DISTURBANCE.

ALL DISTURBED AREAS LEFT MULCHED AFTER 30 DAYS SHALL BE STABILIZED WITH TEMPORARY VEGETATION.

SEDIMENT AND EROSION CONTROL MEASURES SHOULD BE CHECKED AFTER EACH RAIN EVENT. EACH DEVICE IS TO BE MAINTAINED OR REPLACED IF SEDIMENT ACCUMULATION HAS REACHED ONE HALF THE CAPACITY OF THE DEVICE. ADDITIONAL DEVICES MUST BE INSTALLED IF NEW CHANNELS HAVE DEVELOPED.

THE CONSTRUCTION EXIT SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACK OR FLOW OF MUD ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 1-3" OF STONE, AS CONDITIONS DEMAND. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM THE VEHICLE ONTO PUBLIC ROADWAY OR INTO STORM DRAIN MUST BE REMOVED IMMEDIATELY.

CONTRACTOR SHALL INSPECT CONTROL MEASURES AT THE END OF EACH WORKING DAY TO ENSURE MEASURES ARE FUNCTIONING PROPERLY.

SEDIMENT SOURCE AS DIRECTED BY THE ON SITE INSPECTOR OR THE CIVIL ENGINEER.

FAILURE TO INSTALL, OPERATE, OR MAINTAIN ALL EROSION CONTROL MEASURES WILL RESULT IN ALL CONSTRUCTION BEING STOPPED ON THE JOB UNTIL SUCH MEASURES ARE CORRECTED BACK TO THE APPROVED EROSION CONTROL PLANS.

INTERMEDIATE PHASE

EROSION CONTROL NOTES:

DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN CAREFUL SCHEDULING AND PERFORMANCE TO ENSURE THAT LAND STRIPPED OF ITS NATURAL GROUND COVER IS EXPOSED ONLY IN SMALL QUANTITIES AND THEREFORE LIMITED DURATION, BEFORE PERMANENT EROSION PROTECTION IS ESTABLISHED. NOTE SUB PHASES SHOWN ON PLANS.

EARTHWORK OPERATIONS IN THE VICINITY OF STREAM BUFFERS SHALL BE CAREFULLY CONTROLLED TO AVOID DUMPING OR SLOUGHING INTO THE BUFFER AREAS.

EROSION CONTROL MEASURES SHALL BE IMPLEMENTED DURING THE PRELIMINARY GRADING PHASE OF CONSTRUCTION.

SEDIMENT TRAPS SHALL BE DISPOSED OF AND STABILIZED SO THAT IT WILL NOT ENTER THE INLETS AGAIN.

EROSION CONTROL DEVICES SHALL BE INSTALLED IMMEDIATELY AFTER GROUND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM THAT SHOWN ON THE APPROVED PLANS IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE PROPOSED DRAINAGE PATTERNS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING CONSTRUCTION. ANY CONSTRUCTION SHALL BE

THE CONTRACTOR SHALL FURNISH AND MAINTAIN ALL NECESSARY BARRICADES WHILE ROADWAY FRONTAGE IMPROVEMENTS ARE BEING MADE.

TYPE "A" SILT FENCE SHOULD BE INSTALLED AT THE TOE OF ALL FILL SLOPES 10 FEET OR GREATER IN HEIGHT. THE SILT FENCE SHOULD BE EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE PLACED IN ACCORDANCE WITH THE MANUAL FOR EROSION CONTROL IN GEORGIA, TABLE 6-20.2. THE SILT FENCES SHALL BE MAINTAINED UNTIL PERMANENT GROUND COVER IS ESTABLISHED ON THE SLOPE. SILT SHALL BE REMOVED WHEN ACCUMULATION REACHES ½ HEIGHT OF THE BARRIER. ADDITIONALLY, DIVERSION DIKES SHALL BE CONSTRUCTED ALONG THE TOP OF ALL SAID FILL SLOPES WITH THE USE OF TEMPORARY DOWN DRAINS TO CONTROL STORM WATER RUN OFF AS SHOWN ON THE PLANS. SEE SEPARATE DETAILS FOR ADDITIONAL INFORMATION.

> THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING BARRIERS AT THE TOE OF SLOPES UNDER CONSTRUCTION. THESE BARRIERS SHALL BE AS SHOWN IN THE PLANS. THESE BARRIERS MAY BE RELOCATED AND REUSED AFTER PERMANENT SLOPE STABILIZATION BECOMES FULLY ESTABLISHED. AS THEY ARE RELOCATED, ANY DEFECTIVE MATERIALS IN THE BARRIER SHALL BE REPLACED. IN ADDITION, ALL DEBRIS AND SILT AT THE PREVIOUS LOCATION SHALL BE REMOVED.

CUT AND FILL SLOPES ARE NOT TO EXCEED "2H: IV".

ALL SLOPES STEEPER THAN 2.5:1 AND WITH A HEIGHT OF TEN FEET OR GREATER, AND CUTS AND FILLS WITHIN STREAM BUFFERS, SHALL BE ESTABLISHED WITH APPROPRIATE EROSION CONTROL MATTING OR BLANKETS. SEE SEPARATE DETAILS FOR ADDITIONAL INFORMATION.

TYPE "A" SILT FENCE SHALL BE PLACED AT THE TOE OF ALL DIRT STOCK PILE AREAS. SEE SEPARATE DETAILS FOR ADDITIONAL INFORMATION.

THE CONTRACTOR SHALL OBSERVE THE PROJECT SEQUENCE SHOWN ON THE PLANS. THE CONTRACTOR SHALL MAINTAIN CAREFUL SCHEDULING INLET SEDIMENT PROTECTION MEASURES SHALL BE INSTALLED ON ALL STORM STRUCTURES AS THEY ARE CONSTRUCTED. SEE PLAN VIEW FOR SPECIFIC TYPE AND SEPARATE DETAILS FOR ADDITIONAL INFORMATION ON TYPE OF INLET PROTECTION SPECIFIED.

> STORM DRAIN OUTLET PROTECTION SHALL BE PLACED AT ALL OUTLET HEADWALLS AS SOON AS THE HEADWALL IS CONSTRUCTED. SEE SEPARATE DETAILS FOR ADDITIONAL INFORMATION.

STONE CHECK DAMS SHALL BE INSTALLED IN AREAS OF CONCENTRATED FLOWS AS SHOWN ON THE PLAN. SEE SEPARATE DETAIL FOR ADDITIONAL INFORMATION.

ALL DRAINAGE SWALES SHALL BE APPLIED WITH VEGETATIVE COVER AS SOON AS FINAL GRADE IS ACHIEVED.

PRIOR TO ANY OTHER CONSTRUCTION, A STABILIZED CONSTRUCTION ENTRANCE SHALL BE CONSTRUCTED AT EACH POINT OF ENTRY TO OR EXIT AFTER PRELIMINARY GRADING ACTIVITIES, THE CONTRACTOR SHALL CONSTRUCT TEMPORARY SEDIMENT BASINS AND DIVERSION DIKES AS SHOWN ON PLAN. THE CONTRACTOR SHALL MAINTAIN THE SEDIMENT POND UNTIL THE PERMANENT GROUND COVER IS ESTABLISHED. SEDIMENT SHALL BE CLEANED OUT OF THE PONDS WHEN IT REACHES THE 1/3 DEPTH OF BASIN. SEE SEPARATE DETAILS FOR ADDITIONAL INFORMATION.

SEDIMENT AND EROSION CONTROL MEASURES SHOULD BE CHECKED AFTER EACH RAIN EVENT. EACH DEVICE IS TO BE MAINTAINED OR

THE CONSTRUCTION EXIT SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACK OR FLOW OF MUD ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 1-3" OF STONE, AS CONDITIONS DEMAND. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLE ONTO PUBLIC ROADWAY OR INTO STORM DRAIN MUST BE REMOVED IMMEDIATELY.

CONTRACTOR SHALL INSPECT CONTROL MEASURES AT THE END OF EACH WORKING DAY TO ENSURE MEASURES ARE FUNCTIONING PROPERLY ALL TIMES AND REPAIRED WHEN REQUESTED BY THE SITE INSPECTOR OR THE PROJECT DESIGN PROFESSIONAL OF RECORD. SILT SHOULD BE EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE

> FAILURE TO INSTALL, OPERATE OR MAINTAIN ALL EROSION CONTROL MEASURES WILL RESULT IN ALL CONSTRUCTION BEING STOPPED ON THE JOB UNTIL SUCH MEASURES ARE CORRECTED BACK TO THE APPROVED EROSION CONTROL PLANS.

EROSION CONTROL NOTES

NEW CHANNELS HAVE DEVELOPED.

THE FOLLOWING EROSION CONTROL MEASURES SHALL BE IMPLEMENTED DURING THE FINAL EROSION CONTROL PHASE OF CONSTRUCTION. SEDIMENT SHALL NOT BE WASHED INTO INLETS. IT SHALL BE REMOVED FROM THE SEDIMENT TRAPS AND DISPOSED OF AND STABILIZED SO THAT

ALL DISTURBED AREAS LEFT MULCHED AFTER 30 DAYS SHALL BE STABILIZED WITH TEMPORARY GRASSING.

SEDIMENT SOURCE AS DIRECTED BY THE ON SITE INSPECTOR OR THE CIVIL ENGINEER.

THE CONTRACTOR SHALL MAINTAIN ALL SEDIMENT PONDS AND EROSION CONTROL MEASURES UNTIL PERMANENT GROUND COVER IS ESTABLISHED. SEDIMENT SHALL BE CLEANED OUT OF THE PONDS WHEN IT REACHES THE HALF WAY POINT ON THE RISER.

AFTER CURBING, GRADED AGGREGATE BASE, AND PAVEMENT HAS BEEN INSTALLED, ALL INLET SEDIMENT TRAPS ON SINGLE AND DOUBLE WING CATCH BASINS ALONG WITH ANY CURB INLETS SHALL BE REMOVED AND REPLACED WITH CURB FILTER INLET PROTECTION. SEE SEPARATE DETAIL FOR ADDITIONAL INFORMATION.

ALL ROADWAY AND PARKING SHOULDERS SHOULD BE APPLIED WITH VEGETATIVE COVER AS SOON AS FINAL GRADE IS ACHIEVED BEHIND CURBS. SEDIMENT AND EROSION CONTROL MEASURES SHOULD BE CHECKED AFTER EACH RAIN EVENT. EACH DEVICE IS TO BE MAINTAINED OR REPLACED IF SEDIMENT ACCUMULATION HAS REACHED ONE HALF THE CAPACITY OF THE DEVICE. ADDITIONAL DEVICES MUST BE INSTALLED IF

THE CONSTRUCTION EXIT SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACK OR FLOW OF MUD ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 1-3" OF STONE, AS CONDITIONS DEMAND. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLE ONTO PUBLIC ROADWAY OR INTO STORM DRAIN MUST BE REMOVED IMMEDIATELY.

CONTRACTOR SHALL INSPECT CONTROL MEASURES AT THE END OF EACH WORKING DAY TO ENSURE MEASURES ARE FUNCTIONING PROPERLY. EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE AS DIRECTED BY THE ON SITE INSPECTOR OR THE CIVIL ENGINEER.

FAILURE TO INSTALL, OPERATE OR MAINTAIN ALL EROSION CONTROL MEASURES WILL RESULT IN ALL CONSTRUCTION BEING STOPPED ON THE JOB UNTIL SUCH MEASURES ARE CORRECTED BACK TO THE APPROVED EROSION CONTROL PLANS.

UPON COMPLETION OF THE PROJECT AND RECEIPT OF CERTIFICATE OF OCCUPANCY, THE CONTRACTOR SHALL REMOVE ALL TEMPORARY EROSION CONTROL MEASURES AND DISPOSE OF THEM UNLESS NOTED ON PLANS.

AT THE END OF EACH WORK DAY, ALL SLOPES 2:1 OR STEEPER AND HIGHER THAN 5 FEET SHALL RECEIVE SURFACE ROUGHENING, POLYMERS, AND EROSION CONTROL MATTING. ADDITIONALLY, ALL FILL SLOPES SHALL RECEIVE A DIVERSION DIKE AND TEMPORARY DOWN DRAINS ALONG EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR THE SLOPE PREVENTING DRAINAGE SPILLING OVER THE EDGE AND DOWN THE FACE OF THE SLOPE. THE TEMPORARY DOWN DRAINS EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SHALL BE CONSTRUCTED WITH PERFORATED STAND PIPES AT THE TOP OF THE SLOPE AND RECONSTRUCTED EACH DAY AS THE SLOPE INCREASES IN HEIGHT.

> DURING CONSTRUCTION PERMANENT GRASSING WILL BE IMPLEMENTED TO CONTROL STORM WATER POLLUTANTS AFTER CONSTRUCTION OPERATIONS HAVE BEEN COMPLETED.

BUILDING MATERIALS AND BUILDING PRODUCTS SHALL BE COVERED WITH A TARP.

NARRATIVE OF LAND DISTURBING ACTIVITY PERMIT FOR:

DESCRIPTION: THE PROPOSED PROJECT IS WITHIN THE R/W OF BRIGGSTON ROAD IN LOWNDES COUNTY, GEORGIA IN LAND LOTS 24, 25, AND 26 OF THE 16th LAND DISTRICT.

EXISTING FEATURES: THE SITE IS CURRENTLY UNPAVED WITH DIRT DITCHES, ACCORDING TO THE SOIL SURVEY FOR LOWNDES COUNTY, THE SITE IS COVERED WITH FUQUAY LOAMY SAND, JOHNSTON LOAM, LEEFIELD LOAMY SAND, MASCOTTE SAND, OLUSTEE SAND, PELHAM LOAMY SAND, & TIFTON LOAMY SAND.

PROPOSED FEATURES: IT IS PROPOSED TO CONSTRUCT A PAVED ROAD WITH ASSOCIATED DRIVEWAYS AND DRAINAGE INFRASTRUCTURE. THE SITE WILL BE GRADED TO MATCH EXISTING ELEVATIONS AS MUCH AS POSSIBLE. STORM WATER WILL BE DIRECTED TO DITCHES AND CULVERTS AND THEN TO OUTFALL LOCATIONS.

STANDARDS AND SPECIFICATIONS: ALL EROSION AND SEDIMENT CONTROL MEASURES WILL CONFORM TO AND WORK WILL BE PERFORMED IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE MANUAL OF EROSION AND SEDIMENT CONTROL IN GEORGIA.

EROSION CONTROL PROGRAM: THE SITE LAYOUT AND GRADING PLAN ARE SUCH THAT CLEARING OF EXISTING VEGETATION WILL BE KEPT TO A MINIMUM. VEGETATION AND MULCH WILL BE APPLIED TO EXPOSED AREAS IMMEDIATELY AFTER GRADING IS COMPLETED.

SEDIMENT CONTROL PROGRAM: SILT FENCING WILL BE INSTALLED ALONG THE LOW SIDES OF GRADED AREAS BEFORE GRADING OPERATIONS TAKE PLACE. ALL DISTURBED AREAS ARE TO BE GRASSED AND MULCHED. A TEMPORARY CONSTRUCTION ENTRANCES/EXIT WILL BE INSTALLED WHERE CONSTRUCTION VEHICLES ENTER AND LEAVE THE SITE.

MAINTENANCE PROGRAM: NO PROBLEMS ARE ANTICIPATED WITH EROSION CONTROL ON THIS SITE PROVIDED THE MEASURES SHOWN ON THE EROSION CONTROL PLAN ARE FOLLOWED AND BEST MANAGEMENT PRACTICES ARE USED DURING CONSTRUCTION. ALL SEDIMENT CONTROL MEASURES WILL REMAIN IN PLACE UNTIL CONTRIBUTING AREAS ARE STABILIZED, ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSPECTED DAILY. ANY DAMAGES OBSERVED WILL BE REPAIRED BY THE END OF THAT DAY. CLEAN OUT OF SEDIMENT CONTROL STRUCTURES WILL BE ACCOMPLISHED IN ACCORDANCE WITH THE SPECIFICATIONS AND THE SEDIMENT DISPOSED OF PROPERLY.

24-HOUR CONTACT: MIKE FLETCHER (229) 671-2424

BRIGGSTON ROAD ROAD



LEVEL II CERT. 8141 DATE: 09/14/2022 DRAWN BY M. WILSON CHECKED BY: B. KENT

SHEET

PROJECT NUMBER

ES&PC NOTES

THIS PLAN HAS BEEN PREPARED TO MEET THE REQUIREMENTS UNDER THE STATE OF GEORGIA, DEPARTMENT OF NATURAL RESOURCES, ENVIRONMENTAL PROTECTION DIVISION (EPD), GENERAL PERMIT NO. GAR 10000I FOR AUTHORIZATION TO DISCHARGE UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES), STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY FOR INFRASTRUCTURE.

1. ALL DISCHARGES OF STORMWATER ASSOCIATED WITH CONSTRUCTION ACTIVITY THAT WILL RESULT IN LAND DISTURBANCE EQUAL TO OR GREATER THAN ONE

2. ALL DISCHARGES COVERED BY THIS PERMIT SHALL BE COMPOSED ENTIRELY OF STORMWATER EXCEPT AS PROVIDED IN PART I.C.2 AND PART III.A.2 OF THE PERMIT. (PART III.A.I)

3. AUTHORIZED MIXED STORMWATER DISCHARGES: (PART I.C.2)

- a. THE INDUSTRIAL SOURCE OR ACTIVITY OTHER THAN CONSTRUCTION IS LOCATED ON THE SAME SITE AS THE CONSTRUCTION ACTIVITY AND IS AN INTEGRAL
- b. THE STORMWATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE AREAS OF THE SITE WHERE CONSTRUCTION ACTIVITIES ARE OCCURRING ARE IN COMPLIANCE WITH THE TERMS OF THE PERMIT.
- c. THE STORMWATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE AREAS OF THE SITE WHERE INDUSTRIAL ACTIVITY OTHER THAN CONSTRUCTION ARE OCCURRING ARE COVERED BY A DIFFERENT NPDES GENERAL PERMIT OR INDIVIDUAL PERMIT AUTHORIZING SUCH DISCHARGES AND THE DISCHARGES ARE IN COMPLIANCE WITH A DIFFERENT NPDES PERMIT
- 4. AUTHORIZED NON-STORMWATER DISCHARGES: (PART III.A.2)
- a. FIRE FIGHTING ACTIVITIES
- b. FIRE HYDRANT FLUSHING
- c. POTABLE WATER SOURCES INCLUDING WATER LINE FLUSHING

CONTRIBUTING TO A VIOLATION OF A WATER QUALITY STANDARD.

- d. IRRIGATION DRAINAGE
- e. AIR CONDITIONING CONDENSATE
- g. UNCONTAMINATED GROUND WATER
- h. FOUNDATION OR FOOTING DRAINS WHERE FLOWS ARE NOT CONTAMINATED WITH PROCESS MATERIALS OR POLLUTANTS

LIMITATIONS ON COVERAGE: (PART I.C.3)

- 1. THE FOLLOWING STORMWATER DISCHARGES FROM CONSTRUCTION SITES ARE NOT AUTHORIZED BY THIS PERMIT
- a. STORMWATER DISCHARGES ASSOCIATED WITH AN INDUSTRIAL ACTIVITY THAT ORIGINATES FROM THE SITE AFTER CONSTRUCTION ACTIVITIES HAVE BEEN COMPLETED AND THE SITE HAS UNDERGONE FINAL STABILIZATION.
- b. DISCHARGES THAT ARE MIXED WITH SOURCES OF NON-STORMWATER OTHER THAN DISCHARGES WHICH ARE IDENTIFIED IN PART III.A.2 OF THIS PERMIT AND WHICH ARE IN COMPLIANCE WITH PART IV.D.7 (NON-STORMWATER DISCHARGES) OF THIS PERMIT.
- c. STORMWATER DISCHARGES ASSOCIATED WITH AN INDUSTRIAL ACTIVITY THAT ARE SUBJECT TO AN EXISTING NPDES INDIVIDUAL OR GENERAL PERMIT. SUCH DISCHARGES MAY BE AUTHORIZED UNDER THIS PERMIT AFTER AN EXISTING PERMIT EXPIRES PROVIDED THE EXISTING PERMIT DID NOT ESTABLISH
- NUMERIC LIMITATIONS FOR SUCH DISCHARGES. d. STORMWATER DISCHARGES FROM CONSTRUCTION SITES THAT THE DIRECTOR (EPD) HAS DETERMINED TO BE OR MAY REASONABLY BE EXPECTED TO BE
- 2. WHERE A RELEASE CONTAINING A HAZARDOUS SUBSTANCE IN AN AMOUNT EQUAL TO OR IN EXCESS OF A REPORTING QUANTITY ESTABLISHED UNDER EITHER GEORGIA'S OIL OR HAZARDOUS MATERIAL SPILLS OR RELEASES ACT (O.C.G.A \$\$12-14-2,ET SEQ). 40 CFR 117 OR 40 CFR 302 OCCURS DURING A 24-HOUR PERIOD, THE PERMITTEE IS REQUIRED TO NOTIFY THE FOLLOWING AGENCIES IN ACCORDANCE WITH THE ABOVE-MENTIONED REGULATIONS AS SOON AS HE HAS KNOWLEDGE OF THE DISCHARGE. EPD AT (404)656-4863 OR (800) 241-4113, OR THE NATIONAL RESPONSE CENTER (NRC) AT (800) 424-8802. (PART III.B.I)
- 3. THIS PERMIT DOES NOT AUTHORIZE THE DISCHARGE OF HAZARDOUS SUBSTANCES OR OIL RESULTING FROM AN ONSITE SPILL. (PART III.B.2)

ALL DISCHARGES AUTHORIZED BY THIS PERMIT SHALL NOT CAUSE VIOLATIONS OF GEORGIA'S IN-STREAM WATER QUALITY STANDARDS AS PROVIDED BY THE RULES AND REGULATIONS FOR WATER QUALITY CONTROL, CHAPTER 391-3-6-03.

1. EACH DAY WHEN ANY TYPE OF CONSTRUCTION ACTIVITY HAS TAKEN PLACE AT A PRIMARY PERMITTEE'S SITE, CERTIFIED PERSONNEL PROVIDED BY THE PRIMARY PERMITTEE SHALL INSPECT: (A) ALL AREAS AT THE PRIMARY PERMITTEE'S SITE WHERE PETROLEUM PRODUCTS ARE STORED. USED. OR HANDLED FOR SPILLS AND LEAKS FROM VEHICLES AND EQUIPMENT: (B) ALL LOCATIONS AT THE PRIMARY PERMITTEE'S SITE WHERE VEHICLES ENTER OR EXIT THE SITE FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING; AND (C) MEASURE RAINFALL ONCE EACH 24 HOUR PERIOD AT THE SITE. THESE INSPECTIONS MUST BE CONDUCTED UNTIL A NOTICE OF TERMINATION IS SUBMITTED.

2. CERTIFIED PERSONNEL (PROVIDED BY THE PRIMARY PERMITTEE) SHALL INSPECT THE FOLLOWING AT LEAST TWICE EVERY SEVEN (7) CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS 0.5 INCHES RAINFALL OR GREATER (UNLESS SUCH STORM ENDS AFTER 5:00 PM ON ANY FRIDAY OR ON ANY NONWORKING SATURDAY, NON-WORKING SUNDAY OR ANY NON-WORKING FEDERAL HOLIDAY IN WHICH CASE THE INSPECTION SHALL BE COMPLETED BY THE END. REPORTS MUST BE SIGNED IN ACCORDANCE WITH PART V.G. SAMPLING REPORTS MUST BE SUBMITTED TO EPD UNTIL SUCH TIME AS A NOT IS SUBMITTED IN OF THE NEXT BUSINESS DAY AND/OR WORKING DAY. WHICHEVER OCCURS FIRST): (A) DISTURBED AREAS OF THE PRIMARY PERMITTEE'S CONSTRUCTION SITE THAT HAVE NOT UNDERGONE FINAL STABILIZATION; (B) AREAS USED BY THE PRIMARY PERMITTEE FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION THAT HAVE NOT UNDERGONE FINAL STABILIZATION; AND (C) STRUCTURAL CONTROL MEASURES. EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN APPLICABLE TO THE PRIMARY PERMITTEE'S SITE SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATER(S). FOR AREAS OF A SITE THAT HAVE UNDERGONE FINAL STABILIZATION, THE PERMITTEE MUST COMPLY WITH PART IV.D.4.A.(3). THESE INSPECTIONS MUST BE CONDUCTED UNTIL A NOTICE OF TERMINATION IS SUBMITTED.

3. CERTIFIED PERSONNEL (PROVIDED BY THE PRIMARY PERMITTEE) SHALL INSPECT AT LEAST ONCE PER MONTH DURING THE TERM OF THIS PERMIT (I.E., UNTIL A NOTICE OF TERMINATION IS RECEIVED BY EPD) THE AREAS OF THE SITE THAT HAVE UNDERGONE FINAL STABILIZATION. THESE AREAS SHALL BE INSPECTED FOR 3. ALL MONITORING RESULTS SHALL INCLUDE THE FOLLOWING INFORMATION: EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM AND THE RECEIVING WATER(S). EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATER(S).

4. BASED ON THE RESULTS OF EACH INSPECTION, THE SITE DESCRIPTION AND THE POLLUTION PREVENTION AND CONTROL MEASURES IDENTIFIED IN THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN, THE PLAN SHALL BE REVISED AS APPROPRIATE NOT LATER THAN SEVEN (7) CALENDAR DAYS FOLLOWING EACH INSPECTION. IMPLEMENTATION OF SUCH CHANGES SHALL BE MADE AS SOON AS PRACTICAL BUT IN NO CASE LATER THAN SEVEN (7) CALENDAR DAYS FOLLOWING EACH INSPECTION.

5. A REPORT OF EACH INSPECTION THAT INCLUDES THE NAME(S) OF PERSONNEL MAKING EACH INSPECTION, THE DATE(S) OF EACH INSPECTION, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN, AND ACTIONS TAKEN IN ACCORDANCE WITH PART IV.D.4.A.(4). OF THE PERMIT SHALL BE MADE AND RETAINED AT THE SITE OR BE READILY AVAILABLE AT A DESIGNATED ALTERNATE LOCATION UNTIL THE ENTIRE SITE OR THAT PORTION OF A CONSTRUCTION PROJECT THAT HAS BEEN PHASED HAS UNDERGONE FINAL STABILIZATION AND A NOTICE OF TERMINATION IS SUBMITTED TO EPD. SUCH REPORTS SHALL IDENTIFY ANY INCIDENTS OF NON-COMPLIANCE. WHERE THE REPORT DOES NOT IDENTIFY ANY INCIDENTS OF NON-COMPLIANCE, THE REPORT SHALL CONTAIN A CERTIFICATION THAT THE CONSTRUCTION SITE IS IN COMPLIANCE WITH THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN AND THIS PERMIT. THE REPORT SHALL BE SIGNED IN ACCORDANCE WITH PART V.G. OF THIS PERMIT.

SAMPLING METHODOLOGY (PART IV.D.6.b):

POINT IS SHOWN ON THE PLAN.

ALL SAMPLING SHALL BE COLLECTED BY "GRAB SAMPLES" AND THE ANALYSIS OF THESE SAMPLES MUST BE CONDUCTED IN ACCORDANCE WITH METHODOLOGY AND TEST PROCEDURES ESTABLISHED BY 40 CFR PART 136 (UNLESS OTHER TEST PROCEDURES HAVE BEEN APPROVED). THE GUIDANCE DOCUMENT TITLED "NPDES STORMWATER SAMPLING GUIDANCE DOCUMENT, EPA 833-B-92-001" AND GUIDANCE DOCUMENTS THAT MAY BE PREPARED BY THE EPD.

1. SAMPLE CONTAINERS SHOULD BE LABELED PRIOR TO COLLECTING THE SAMPLES.

2. LARGE MOUTH, CLEAN AND RINSED GLASS OR PLASTIC JARS WITH A MINIMUM SAMPLE SIZE OF 200 MILLILITERS SHOULD BE USED FOR COLLECTING SAMPLES. 3. SAMPLES SHOULD BE TAKEN FROM THE HORIZONTAL AND VERTICAL CENTER OF THE RECEIVING WATER(S) OR THE STORMWATER OUTFALL CHANNEL(S).

4. SAMPLES SHOULD BE WELL MIXED BEFORE TRANSFERRING TO A SECONDARY CONTAINER 5. MANUAL, AUTOMATIC OR RISING STAGE SAMPLING MAY BE UTILIZED. SAMPLES REQUIRED BY THIS PERMIT SHOULD BE ANALYZED IMMEDIATELY, BUT IN NO

CASE LATER THAN 48 HOURS AFTER COLLECTION. HOWEVER, SAMPLES FROM AUTOMATIC SAMPLERS MUST BE COLLECTED NO LATER THAN THE NEXT BUSINESS DAY AFTER THE ACCUMULATION, UNLESS FLOW THROUGH AUTOMATED ANALYSIS IS UTILIZED. 6. IF MANUAL SAMPLING IS EMPLOYED, THE SAMPLING CONTAINER SHOULD BE HELD SO THAT THE OPENING FACES UPSTREAM. THE SAMPLES SHOULD BE KEPT

FREE FROM FLOATING DEBRIS, AND CARE SHOULD BE TAKEN TO AVOID STIRRING THE BOTTOM SEDIMENTS IN THE RECEIVING WATER(S) OR IN THE OUTFALL STORM WATER CHANNEL 7. THE UPSTREAM SAMPLE FOR EACH RECEIVING WATER(S) MUST BE TAKEN AT THE DISCHARGE FARTHEST UPSTREAM AT THE SITE BUT DOWNSTREAM OF ANY OTHER STORM WATER DISCHARGES NOT ASSOCIATED WITH THE PERMITTED ACTIVITY. WHERE APPROPRIATE, SEVERAL UPSTREAM SAMPLES FROM ACROSS

THE RECEIVING WATER(S) MAY NEED TO BE TAKEN AND THE ARITHMETIC AVERAGE OF THE TURBIDITY OF THESE SAMPLES USED FOR THE UPSTREAM

8. THE DOWNSTREAM SAMPLES FOR EACH RECEIVING WATER(S) MUST BE TAKEN AT THE DISCHARGE FARTHEST DOWNSTREAM AT THE SITE BUT UPSTREAM OF ANY OTHER STORM WATER DISCHARGE NOT ASSOCIATED WITH THE PERMITTED ACTIVITY. WHERE APPROPRIATE, SEVERAL DOWNSTREAM SAMPLES FROM ACROSS THE RECEIVING WATER(S) MAY NEED TO BE TAKEN AND THE ARITHMETIC AVERAGE OF THE TURBIDITY OF THESE SAMPLES USED FOR THE

DOWNSTREAM TURBIDITY VALUE. 9. PERMITTEE'S DO NOT HAVE TO SAMPLE SHEET FLOW THAT FLOWS ONTO UNDISTURBED NATURAL AREAS OR AREAS STABILIZED BY THE PROJECT.

10. DILUTION OF SAMPLES IS NOT REQUIRED.

11. SAMPLES MAY BE ANALYZED USING A DIRECT READING, PROPERLY CALIBRATED TURBIDIMETER.

12. SAMPLES ARE NOT REQUIRED TO BE COOLED.

13. SAMPLING AND ANALYSIS OF THE RECEIVING WATER(S) OR OUTFALLS BEYOND THE MINIMUM FREQUENCY STATED IN THE PERMIT MUST BE REPORTED TO EPD AS SPECIFIED IN PART IV.E OF THE PERMIT.

14. TURBIDITY RESULTS WHICH EXCEED 1000 NTU SHALL BE REPORTED AS "EXCEEDS 1000 NTU."

SAMPLING FREQUENCY (PART IV.D.5D):

1. SAMPLING FREQUENCY SHALL OCCUR IN ACCORDANCE WITH PART IV.D.5.D OF THE PERMIT.

2. FOR A QUALIFYING EVENT, SAMPLES MUST BE TAKEN WITHIN FORTY-FIVE (45) MINUTES OF:

a. THE ACCUMULATION OF THE MINIMUM AMOUNT OF RAINFALL FOR THE QUALIFYING EVENT, IF THE STORM WATER DISCHARGE TO A MONITORED RECEIVING WATER OR FROM A MONITORED OUTFALL HAS BEGUN PRIOR TO THE ACCUMULATION.

b. THE BEGINNING OF ANY STORM WATER DISCHARGE TO A MONITORED RECEIVING WATER OR FROM A MONITORED OUTFALL IF THE DISCHARGE BEGINS AFTER THE ACCUMULATION OF THE MINIMUM AMOUNT OF RAINFALL FOR THE QUALIFYING EVENT.

c. WHERE MANUAL AND AUTOMATIC SAMPLING ARE NOT IMPOSSIBLE (AS DEFINED IN THE PERMIT), OR ARE BEYOND THE PERMITTEE'S CONTROL, THE PERMITTEE SHALL TAKE SAMPLES AS SOON AS POSSIBLE, BUT IN NO CASE MORE THAN TWELVE (12) HOURS AFTER THE BEGINNING OF THE STORM WATER

d. NORMAL BUSINESS HOURS, AS DEFINED BY THE PERMIT, ARE MONDAY THROUGH FRIDAY, 8:00AM TO 5:00 PM AND SATURDAY 8:00 AM TO 5:00 PM WHEN CONSTRUCTION ACTIVITY IS BEING CONDUCTED BY THE PRIMARY PERMITTEE.

3. SAMPLING SHALL OCCUR FOR THE FOLLOWING QUALIFYING EVENTS FOR EACH AREA OF THE SITE THAT DISCHARGES TO A RECEIVING STREAM:

a. THE FIRST RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH AND ALLOWS FOR MONITORING DURING NORMAL BUSINESS HOURS THAT OCCURS AFTER ALL CLEARING AND GRUBBING OPERATIONS HAVE BEEN COMPLETED IN THE DRAINAGE AREA OF THE LOCATION SELECTED AS THE REPRESENTATIVE SAMPLING

b. THE FIRST RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH AND ALLOWS FOR MONITORING DURING NORMAL BUSINESS HOURS THAT OCCURS EITHER 90 DAYS AFTER THE FIRST SAMPLING EVENT OR AFTER ALL MASS GRADING OPERATIONS HAVE BEEN COMPLETED IN THE DRAINAGE AREA OF THE LOCATION SELECTED AS THE REPRESENTATIVE SAMPLING LOCATION.

4. IF BMPS IN ANY AREA OF THE SITE THAT DISCHARGES TO A RECEIVING STREAM ARE NOT PROPERLY DESIGNED, INSTALLED AND MAINTAINED, CORRECTIVE ACTION SHALL BE DEFINED AND IMPLEMENTED WITH 2 BUSINESS DAYS, AND TURBIDITY SAMPLES SHALL BE TAKEN FROM DISCHARGES FROM THAT AREA OF THE SITE FOR EACH SUBSEQUENT RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH DURING NORMAL BUSINESS HOURS UNTIL THE SELECTED TURBIDI STANDARD IS ATTAINED, OR UNTIL POST-STORM EVENT INSPECTIONS DETERMINE THAT BMPS ARE PROPERLY DESIGNED, INSTALLED AND MAINTAINED.

THE PERMITTEE MAY CHOOSE TO MEET THE REQUIREMENTS OF NO. 5.1 AND NO.5.2 BY COLLECTING TURBIDITY SAMPLES FROM ANY RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH AND ALLOWS FOR MONITORING AT ANY TIME OF THE DAY OR WEEK.

REPORTING (PART IV.E):

1. THE APPLICABLE PERMITTEES ARE REQUIRED TO SUBMIT A SUMMARY OF THE MONITORING RESULTS TO THE EPD AT THE ADDRESS SHOWN IN PART II.C. BY THE FIFTEENTH DAY OF THE MONTH FOLLOWING THE REPORTING PERIOD. REPORTING PERIODS ARE MONTHS DURING WHICH SAMPLES ARE TAKEN IN ACCORDANCE WITH THIS PERMIT. SAMPLING RESULTS SHALL BE IN A CLEARLY LEGIBLE FORMAT. UPON WRITTEN NOTIFICATION, EPD MAY REQUIRE THE APPLICABLE PERMITTEE TO SUBMIT THE SAMPLING RESULTS ON A MORE FREQUENT BASIS. SAMPLING AND ANALYSIS OF ANY STORM WATER DISCHARGE(S) OR THE RECEIVING WATER(S) BEYOND THE MINIMUM FREQUENCY STATED IN THIS PERMIT MUST BE REPORTED IN A SIMILAR MANNER TO THE EPD. THE SAMPLING ACCORDANCE WITH PART VI.

2. ALL WRITTEN CORRESPONDENCE REQUIRED BY THIS PERMIT SHALL BE SUBMITTED BY RETURN RECEIPT CERTIFIED MAIL (OR SIMILAR SERVICE) TO THE APPROPRIATE DISTRICT OFFICE OF THE EPD ACCORDING TO THE SCHEDULE IN APPENDIX A OF THIS PERMIT. THE PERMITTEE SHALL RETAIN A COPY OF THE PROOF OF SUBMITTAL AT THE CONSTRUCTION SITE OF THE PROOF OF SUBMITTAL SHALL BE READILY AVAILABLE AT A DESIGNATED LOCATION FROM COMMENCEMENT OF CONSTRUCTION UNTIL SUCH TIME AS A NOT IS SUBMITTED IN ACCORDANCE WITH PART VI.

A. THE DATE, EXACT PLACE, AND TIME OF SAMPLING OR MEASUREMENT;

B. THE NAME(S) OF THE INDIVIDUAL(S) WHO PERFORMED THE SAMPLING AND MEASUREMENTS

C. THE DATE(S) ANALYSES WERE PERFORMED;

D. THE TIME(S) ANALYSIS WERE INITIATED;

E. THE NAME(S) OF THE INDIVIDUAL(S) WHO PERFORMED THE ANALYSIS;

F. REFERENCES AND WRITTEN PROCEDURES, WHEN AVAILABLE, FOR THE ANALYTICAL TECHNIQUES OR METHODS USED; AND G. THE RESULTS OF SUCH ANALYSIS, INCLUDING THE BENCH SHEETS, INSTRUMENT READOUTS, COMPUTER DISKS OR TAPES, ETC. USED TO DETERMINE

THESE RESULTS.

H. RESULTS WHICH EXCEED 1000 NTU SHALL BE REPORTED AS "EXCEEDS 1000 NTU."

RETENTION OF RECORDS (PART IV.F):

1. THE PRIMARY PERMITTEE SHALL RETAIN THE FOLLOWING RECORDS AT THE CONSTRUCTION SITE OR THE RECORDS SHALL BE READILY AVAILABLE AT A DESIGNATED ALTERNATE LOCATION FROM COMMENCEMENT OF CONSTRUCTION UNTIL SUCH TIME AS A NOT IS SUBMITTED IN ACCORDANCE WITH PART VI: A. A COPY OF ALL NOTICES OF INTENT SUBMITTED TO EPD:

B. A COPY OF THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN REQUIRED BY THIS PERMIT;

C. THE DESIGN PROFESSIONAL'S REPORT OF THE RESULTS OF THE INSPECTION CONDUCTED IN ACCORDANCE WITH PART IV.A.5. OF THIS PERMIT;

D. A COPY OF ALL MONITORING INFORMATION, RESULTS, AND REPORTS REQUIRED BY THIS PERMIT E. A COPY OF ALL INSPECTION REPORTS GENERATED IN ACCORDANCE WITH PART IV.D.4.a. OF THIS PERMIT

F. A COPY OF ALL VIOLATION SUMMARIES AND VIOLATION SUMMARY REPORTS GENERATED IN ACCORDANCE WITH PART III.D.2 OF THIS PERMIT; AND

G. DAILY RAINFALL INFORMATION COLLECTED IN ACCORDANCE WITH PART IV.D.4.a.(1)(c) OF THIS PERMIT

2. COPIES OF ALL NOTICES OF INTENT, NOTICES OF TERMINATION, REPORTS, PLANS, MONITORING REPORTS, MONITORING INFORMATION, INCLUDING ALI CALIBRATION AND MAINTENANCE RECORDS AND ALL ORIGINAL STRIP CHART RECORDINGS FOR CONTINUOUS MONITORING INSTRUMENTATION, EROSION, SEDIMENTATION AND POLLUTION CONTROL PLANS, RECORDS OF ALL DATA USED TO COMPLETE THE NOTICE OF INTENT TO BE COVERED BY THIS PERMIT AND ALL OTHER RECORDS REQUIRED BY THIS PERMIT SHALL BE RETAINED BY THE PERMITTEE WHO EITHER PRODUCED OR USED IT FOR A PERIOD OF AT LEAST THREE YEARS FROM THE DATE THAT THE THE NOT IS SUBMITTED IN ACCORDANCE WITH PART VI OF THIS PERMIT. THESE RECORDS MUST BE MAINTAINED AT THE PERMITTEE'S PRIMARY PLACE OF BUSINESS OR AT A DESIGNATED ALTERNATIVE LOCATION ONE THE CONSTRUCTION ACTIVITY HAS CEASED AT THE PERMITTED SITE. THIS PERIOD MAY BE EXTENDED BY REQUEST OF EPD AT ANY TIME UPON WRITTEN NOTIFICATION TO THE PERMITTEE.

POTENTIAL POLLUTANTS

THE FOLLOWING POTENTIAL POLLUTANTS TYPICALLY IDENTIFIED WITH CONSTRUCTION MAY BE PRESENT ON-SITE. POLLUTION PREVENTION MEASURES IMPLEMENTED, AS PART OF THIS PLAN WILL REDUCE THE POTENTIAL FOR CONTACT OF THESE POLLUTANTS WITH STORMWATER.

PETROLEUM PRODUCTS

CONSTRUCTION DEBRIS

FERTILIZERS

PAINTS AND RELATED MATERIALS

CHLORINATED WATER LINE FLUSHING

SANITARY WASTE

SPILL PREVENTION:

MATERIAL MANAGEMENT PRACTICES:

GOOD HOUSEKEEPING: THE FOLLOWING GOOD HOUSEKEEPING PRACTICES SHALL BE FOLLOWED ONSITE DURING THE CONSTRUCTION PROJECT.

AN EFFORT SHALL BE MADE TO STORE ONLY ENOUGH OF ANY PRODUCT UTILIZED ONSITE AS IS REQUIRED TO DO THE JOB.

• ALL MATERIALS STORED ONSITE SHALL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER ENCLOSURE.

PRODUCTS SHALL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURER'S LABEL.

SUBSTANCES SHALL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER.

WHENEVER POSSIBLE, ALL OF A PRODUCT SHALL BE USED UP BEFORE DISPOSING OF THE CONTAINER.

MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL SHALL BE FOLLOWED.

• THE SITE SUPERINTENDENT SHALL INSPECT DAILY TO ENSURE PROPER USE AND DISPOSAL OF MATERIALS ONSITE.

HAZARDOUS PRODUCTS:

HAZARDOUS PRODUCTS USED ON-SITE SHALL BE KEPT IN ORIGINAL CONTAINERS UNLESS THEY ARE NOT RESEALABLE

• ORIGINAL LABELS AND MATERIAL SAFETY DATA SHEETS (MSDS) SHALL BE RETAINED ON SITE.

SURPLUS HAZARDOUS PRODUCTS SHALL BE DISPOSED OF ACCORDING TO LOCAL, STATE, AND FEDERAL GUIDELINES.

• ALL VEHICLES SHALL BE MONITORED FOR PETROLEUM LEAKS.

PETROLEUM PRODUCTS UTILIZED ON-SITE SHALL BE STORED APPROPRIATELY.

ASPHALT SUBSTANCES UTILIZED ON-SITE SHALL BE APPLIED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.

• FERTILIZERS USED FOR ENHANCEMENT OF STABILIZATION MEASURES SHALL BE APPLIED ACCORDING TO APPLICABLE RATE SCHEDULES.

• FERTILIZERS SHALL BE "WORKED" INTO THE SOIL TO MINIMIZE EXPOSURE TO STORMWATER FERTILIZER MATERIALS STORED ON-SITE SHALL BE MANAGED IN A MANNER TO REDUCE THE POTENTIAL FOR STORMWATER CONTAMINATION.

• PAINT MATERIALS ON-SITE SHALL BE STORED IN TIGHTLY SEALED CONTAINERS.

EXCESS PAINT AND PAINT WASTE SHALL BE DISPOSED OF ACCORDING TO APPLICABLE LOCAL, STATE, AND FEDERAL GUIDELINES.

CONCRETE TRUCKS:

ON-SITE DISCHARGE OF DRUM WASH FROM CONCRETE TRUCKS IS PROHIBITED.

SPILL CONTROL PRACTICES:

IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTIONS OF THIS PLAN. THE FOLLOWING PRACTICES SHALL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP:

• MANUFACTURERS' RECOMMENDED METHODS FOR SPILL CLEANUP SHALL BE CLEARLY POSTED AND SITE PERSONNEL SHALL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES.

MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP SHALL BE KEPT IN MATERIAL STORAGE AREA ONSITE.

• ALL SPILLS SHALL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY.

• SPILLS OF TOXIC OR HAZARDOUS MATERIAL SHALL BE REPORTED TO THE APPROPRIATE FEDERAL, STATE, OR LOCAL GOVERNMENT AGENCY, REGARDLESS

OF THE SIZE. • THE SPILL PREVENTION PLAN SHALL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT SPILLS FROM REOCCURRING AND HOW TO CLEAN UP THE SPILL IF THERE IS ANOTHER ONE. A DESCRIPTION OF THE SPILL, WHAT CAUSED IT, AND THE CLEAN UP MEASURES SHALL ALSO BE INCLUDED.

• THE SITE SUPERINTENDENT RESPONSIBLE FOR THE DAY-TO-DAY OPERATIONS SHALL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR.

AMPLING POINT(S):
HE APPROXIMATE LOCATION OF EACH MONITORING MONITORING POINTS: LOCATED UPSTREAM & DOWNSTREAM OF STORM STRUCTURE ST2.

APPENDIX B RATIONAL: NUMBER OF OUTFALLS: 1

DISTURBED AREA: 11.50 AC.

SURFACE WATER DRAINAGE AREA: <5 SQ. MI. YPE OF RECEIVING WATER: WARM WATER FISHERIES

LEVEL II CERT. 8141 M. WILSON CHECKED BY: B. KENT

> 33 of 47PROJECT NUMBER

NPDES NOTES

	REVISIONS
DATE:	DESCRIPTION:
02/24/2023	REVISIONS PER COUNTY COMMENTS
03/30/2023	REVISIONS PER COUNTY COMMENTS
06/12/2023	REVISIONS PER COUNTY COMMENTS
07/05/2023	REVISIONS PER GDOT COMMENTS
07/14/2023	REVISIONS PER GDOT COMMENTS
© COPYRIGHT 2022 THIS DRAWING IS T	© COPYRIGHT 2022 THIS DRAWING IS THE PROPERTY OF INNOVATE ENGINEERING & SURVEYING,
LLC. AND MAY	LLC. AND MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION.
POCTIMENTS	DOCTIMENTS OF PITRI IC RECORD MAY BE CODIFD BITT NOT AT TERED

		PHO 2214
, elle	EORG REGISTERED NO. 22564 PROFESSIONA ENGINEER AMD.	

LEVEL II CERT. 8141 **CHECKED BY:** B. KENT

 $34 \, \mathrm{of} \, 47$

PROJECT NUMBER 1669

EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN CHECKLIST INFRASTRUCTURE CONSTRUCTION PROJECTS BRIGGSTON ROAD BRIGGSTON ROAD Date on Plans: <u>7/15/2022</u> Name & email of person filling out checklist: BILL KENT / bkent@innovatees.com TO BE SHOWN ON ES&PC PLAN 1 The applicable Erosion, Sedimentation and Pollution Control Plan Checklist established by the Commission as of January 1 28 Description of the practices that will be used to reduce the pollutants in storm water discharges. * of the year in which the land-disturbing activity was permitted. 29 Description and chart or timeline of the intended sequence of major activities which disturb soils for the major portions of (The completed Checklist must be submitted with the ES&PC Plan or the Plan will not be reviewed) the site (i.e., initial perimeter and sediment storage BMPs, clearing and grubbing activities, excavation activities, utility 2 Level II certification number issued by the Commission, signature and seal of the certified design professional. activities, temporary and final stabilization). (Signature, seal and level II number must be on each sheet pertaining to ES&PC Plan or the Plan will not be reviewed) 30 Provide complete requirements of Inspections and record keeping by the primary permittee. * 3 The name and phone number of the 24-hour contact responsible for erosion, sedimentation and pollution controls. 31 Provide complete requirements of Sampling Frequency and Reporting of sampling results. * 4 Provide the name, address, email address, and phone number of primary permittee. 32 Provide complete details for Retention of Records as per Part IV.F. of the permit. * 5 Note total and disturbed acreages of the project or phase under construction. 33 Description of analytical methods to be used to collect and analyze the samples from each location. * 6 Provide the GPS locations of the beginning and end of the Infrastructure project. Give the Latitude and Longitude in 34 Appendix B rationale for NTU values at all outfall sampling points where applicable. * 35 Delineate all sampling locations, perennial and intermittent streams and other water bodies into which storm water is 7 Initial date of the Plan and the dates of any revisions made to the Plan including the entity who requested the revisions. discharged also provide a summary chart of the justification and analysis for the representative sampling as applicable. 8 Descriptions of the nature of construction activity and existing site conditions. 36 A description of appropriate controls and measures that will be implemented at the construction site including: (1) initial 9 Provide vicinity map showing site's relation to surrounding areas. Include designation of specific phase, if necessary. sediment storage requirements and perimeter control BMPs, (2) intermediate grading and drainage BMPs, and (3) final 10 Identify the project receiving waters and describe all sensitive adjacent areas including streams, lakes, residential areas, BMPs. For construction sites where there will be no mass grading and the initial perimeter control BMPs, wetlands, marshlands, etc. which may be affected. intermediate grading and drainage BMPs, and final BMPs are the same, the Plan may combine all of the BMPs into a single 11 Design professional's certification statement and signature that the site was visited prior to development of the ES&PC Plan as stated on Part IV page 21 of the permit. 37 Graphic scale and North arrow. 12 Design professional's certification statement and signature that the permittee's ES&PC Plan provides for an appropriate 38 Existing and proposed contour lines with contour lines drawn at an interval in accordance with the following: and comprehensive system of BMPs and sampling to meet permit requirements as stated on Part IV page 20 of the permit. * Existing Contours USGS 1": 2000' Topographical Sheets Proposed Contours 1": 400' Centerline Profile 13 Design professional certification statement and signature that the permittee's ES&PC Plan provides for representative N/A 39 Use of alternative BMPs whose performance has been documented to be equivalent to or superior to conventional BMPs sampling as stated on Part IV.D.6.c.(3) page 37 of the permit as applicable. * as certified by a Design Professional (unless disapproved by GAEPD or the Georgia Soil and Water Conservation 14 Clearly note the statement that "The design professional who prepared the ES&PC Plan is to inspect the installation of the Commission). Please refer to the Alternative BMP Guidance Document found at www.gaswcc.georgia.gov. initial sediment storage requirements, perimeter control BMPs, and sediment basins within 7 days after installation." in accordance with Part IV.A.5 page 26 of the permit * N/A 40 Use of alternative BMP for application to the Equivalent BMP List. Please refer to Appendix A-2 of the Manual for Erosion & Sediment Control in Georgia 2016 Edition. * 15 Clearly note the statement that "Non-exempt activities shall not be conducted within the 25 or 50-foot undisturbed stream buffers as measured from the point of wrested vegetation or within 25-feet of the coastal marshland buffer as measured 41 Delineation of the applicable 25-foot or 50-foot undisturbed buffers adjacent to State waters and any additional buffers from the Jurisdictional Determination Line without first acquiring the necessary variances and permits." required by the Local Issuing Authority. Clearly note and delineate all areas of impact 16 Provide a description of any buffer encroachments and indicate whether a buffer variance is required. 42 Delineation of on-site wetlands and all State waters located on and within 200 feet of the project site. 17 Clearly note the statement that "Amendments/revisions to the ES&PC Plan which have a significant effect on BMPs with a 43 Delineation and acreage of contributing drainage basins on the project site. hydraulic component must be certified by the design professional." * 44 Delineate on-site drainage and off-site watersheds using USGS 1":2000' topographical sheets. 18 Clearly note the statement that "Waste materials shall not be discharged to waters of the State, except as authorized by a 45 An estimate of the runoff coefficient or peak discharge flow of the site prior to and after construction activities are Section 404 permit * 19 Clearly note statement that "The escape of sediment from the site shall be prevented by the installation of erosion and 46 Storm-drain pipe and weir velocities with appropriate outlet protection to accommodate discharges without erosion. sediment control measures and practices prior to land disturbing activities." Identify/Delineate all storm water discharge points. 20 Clearly note statement that "Erosion control measures will be maintained at all times. If full implementation of the approved 31 25-29 47 Soil series for the project site and their delineation. Plan does not provide for effective erosion control, additional erosion and sediment control measures shall be implemented 48 The limits of disturbance for each phase of construction. to control or treat the sediment source." 49 Provide a minimum of 67 cubic yards of sediment storage per acre drained using a temporary sediment basin, 21 Clearly note the statement "Any disturbed area left exposed for a period greater than 14 days shall be stabilized with mulch retrofitted detention pond, and/or excavated inlet sediment traps for each common drainage location. Sediment storage or temporary seeding." volume must be in place prior to and during all land disturbance activities until final stabilization of the site has been 22 Any construction activity which discharges storm water into an Impaired Stream Segment, or within 1 linear mile upstream achieved. A written justification explaining the decision to use equivalent controls when a sediment basin is not attainable of and within the same watershed as, any portion of a Biota Impaired Stream Segment must comply with Part III. C. of the must be included in the Plan for each common drainage location in which a sediment basin is not provided. A written permit. Include the completed Appendix 1 listing all the BMPs that will be used for those areas of the site which discharge justification as to why 67 cubic yards of storage is not attainable must also be given. Worksheets from the Manual must be to the Impaired Stream Segment. * included for structural BMPs and all calculations used by the design professional to obtain the required sediment storage N/A 23 If a TMDL Implementation Plan for sediment has been finalized for the Impaired Stream Segment (identified in item 22 when using equivalent controls. When discharging from sediment basins and impoundments, permittees are required to above) at least six months prior to submittal of NOI, the ES&PC Plan must address any site-specific conditions or utilize outlet structures that withdraw water from the surface, unless infeasible. If outlet structures that withdraw water from requirements included in the TMDL Implementation Plan. * the surface are not feasible, a written justification explaining this decision must be included in the Plan. 24 BMPs for concrete washdown of tools, concrete mixer chutes, hoppers and the rear of the vehicles. Washout of the drum 50 Location of Best Management Practices that are consistent with and no less stringent than the Manual for Erosion and at the construction site is prohibited. * Sediment Control in Georgia. Use uniform coding symbols from the Manual, Chapter 6, with legend. 25 Provide BMPs for the remediation of all petroleum spills and leaks. 51 Provide detailed drawings for all structural practices. Specifications must, at a minimum, meet the guidelines set forth in the Manual for Erosion and Sediment Control in Georgia. 26 Description of the measures that will be installed during the construction process to control pollutants in storm water that will occur after construction operations have been completed. * 52 Provide vegetative plan, noting all temporary and permanent vegetative practices. Include species, planting dates and seeding, fertilizer, lime and mulching rates. Vegetative plan shall be site specific for appropriate time of year that seeding 27 Description of practices to provide cover for building materials and building products on site. *


will take place and for the appropriate geographic region of Georgia.


but within 200 ft of a perennial stream, the * checklist items would be N/A.


* If using this checklist for a project that is less than 1 acre and not part of a common development


Effective January 1, 2022


ES&PC CHECKLIST































DATE:
09/14/2022
DRAWN BY:
M. WILSON
CHECKED BY:
B. KENT


CONSTRUCTION DETAILS

 $45 \, \mathrm{of} \, 47$ PROJECT NUMBER 1669












DATE: 09/14/2022 DRAWN BY: M. WILSON CHECKED BY: B. KENT

SHEET $46 \, \mathrm{or} \, 47$

PROJECT NUMBER 1669







DATE: 09/14/2022 DRAWN BY: M. WILSON CHECKED BY: B. KENT

47 of 47PROJECT NUMBER 1669

SHEET

PROPOSED RAILROAD CROSSING