

ENG 2024-01: 2024 Resurfacing  
Project Information Sheet

**\*\*\* Meadow Woods Subdivision \*\*\***

**Eastridge Drive – 0.21 Miles – 22’ wide – Beginning at CR 29 (Clyattstone Road) Ending at Dead End**

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4” wide – once after leveling
- Temporary centerline stripe 4” wide – once after topping
- Permanent centerline stripe 5” wide – 15 days after topping

**Laurelwood North – 0.05 Miles – 22’ wide – Beginning at CR 967 (Summer Field Drive) Ending at Dead End**

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4” wide – once after leveling
- Temporary centerline stripe 4” wide – once after topping
- Permanent centerline stripe 5” wide – 15 days after topping
- 1 Stop Bar (24” Thermoplastic)

**Laurelwood South – 0.13 Miles – 22’ wide – Beginning at CR 967 (Summer Field Drive) Ending at Dead End**

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4” wide – once after leveling
- Temporary centerline stripe 4” wide – once after topping
- Permanent centerline stripe 5” wide – 15 days after topping
- 1 Stop Bar (24” Thermoplastic)